PHYSICAL ENGINEERING'S LAST EXAM · PUBLIC DEV SET · 29 TASKS

# What was measured, and what was not

A report on all 29 PLE development tasks

**Agent AIODAM** · own harness · model DeepSeek V4.1 Flash

11 November 2026 · Report 1.0 · dataset dev split v0.4.6

| 29 | 15 | 14 | 0 |
|---|---|---|---|
| tasks reported | with a measured machine score | documents, no judge score | LLM-judge scores anywhere |

This report separates machine scores, judge scores, stub-judge simulations and my own checks. It is not a leaderboard submission, and it does not call a host run a container run. Every score in it is traceable to a file and a hash.

# Contents

**What this report is** 3
**What PLE is** 4
**All 29 tasks at a glance** 5
**How the work was done** 8
**How to read a score** 9
**The verification ladder** 10
**Limits stated up front** 11
**Part A — checks tasks** 11
T-01 — cooling-water-flush-plan 11
T-02 — data-center-site-model 12
T-03 — data-hall-device-takeoff 14
T-04 — data-hall-mep-routing 15
T-05 — data-hall-mep-routing-offset 16
T-06 — division-26-specifications 17
T-07 — frame-extension-method 18
T-08 — heat-rejection-life-cycle-cost 19
T-09 — mv-conveyance-study 20
T-10 — roof-deck-design 21
T-11 — seismic-diaphragm-shear 22
T-12 — wind-diaphragm-shear 23
**Part B — checks-judge tasks** 24
T-13 — eor-review-corrections 24
T-14 — foundation-strategy 25
T-15 — lv-cable-sizing 26
**Part C — rubric tasks** 27
T-16 — backfeed-energization-reply 27
T-17 — emergency-spillway-check 28
T-18 — engineers-estimate-check 29
T-19 — fill-compaction-acceptance 30
T-20 — fire-solve-convergence 31
T-21 — fire-test-validation-memo 32
T-22 — footing-settlement-verification 33
T-23 — landscape-sheet-revision 34
T-24 — les-mesh-resolution 35
T-25 — permission-to-operate-memo 36
T-26 — pre-application-capacity-response 37
T-27 — shoring-design-verification 38
T-28 — solar-supplemental-review 39
T-29 — solar-witness-test-package 40
**Cross-cutting lessons** 42
**Conclusions** 43
**Sources and supporting files** 44
**Appendix A — measured score ledger** 45
**Appendix B — rubric packages** 46
**Appendix C — the host's walls** 47
**Appendix D — glossary** 48

# What this report is

This report describes work on all 29 tasks of the public development set of Physical Engineering’s Last Exam (PLE). It is written for a reader who has not seen the working conversation and does not know how the working files are organised. Every task gets the same treatment: what was asked and what data existed, what was ambiguous or broken, what was actually done and with what result, how the result was checked and what mistakes were found, and which score — if any — was really measured.

It is a lab notebook turned into a report, not a leaderboard entry. Three things are deliberately kept apart throughout: scores produced by the task’s own deterministic grader; scores that require an external language-model judge; and my own checks, which are evidence about a document but never a score. Where no score exists, the report says so instead of estimating one.

The work was carried out by the agent AIODAM, running on its own harness — its own tool-calling runtime with shell, file, process and artifact tools — with the DeepSeek V4.1 Flash model. Every number below was produced by a command executed in that harness and is traceable to a file on disk.

# What PLE is

PLE is a benchmark of long-horizon engineering tasks written by licensed practising engineers across four disciplines: civil/structural, mechanical, electrical and architectural/site. Each task is a self-contained Harbor folder that drops the agent into a realistic project workspace — drawings, specifications, spreadsheets, solver scripts, CAD/BIM models, correspondence — and asks for a professional deliverable: a calculation package, a model, a schedule, a specification, a technical memo.

The public development set contains 29 of the benchmark's 85 tasks (release 0.4.6, split dev): 33,416 files, 954,423,732 bytes. Every task allows six hours of agent time with no internet access beyond model API calls, and is graded from 0 to 1 inside an isolated verifier container. The set is access-gated and the repository asks that it not be redistributed; this report therefore cites files by path and hash rather than reproducing task content.

The 29 tasks divide by grading type into 12 checks tasks (a deterministic grader), 14 rubric tasks (an LLM judge scores a document against weighted criteria) and 3 checks-judge tasks (a grader plus a small number of judge families). The judge model named in the task configuration is claude-opus-5-5.

# All 29 tasks at a glance

Twenty-nine tasks: 12 checks, 3 checks-judge, 14 rubric. Fifteen have a measured machine score; five of those are exactly 1.000; the mean final reward is 0.906 and the mean grader score is 0.866. Fourteen have a hashed document and no score, because the judge was never available.

| # | Task | Type | Deliverable | G grader | R final | Judge | Status |
|---|---|---|---|---|---|---|---|
| T-01 | **cooling-water-flush-plan** | checks | `output/submission.zip`<br>`10,349 B` | 0.9238 | 0.9492 | — | measured |
| T-02 | **data-center-site-model** | checks | `submission/model.ifc`<br>`10,328 B` | 1.0000 | 1.0000 | — | measured |
| T-03 | **data-hall-device-takeoff** | checks | `output/submission.zip`<br>`8,748 B` | 0.9699 | 0.9699 | — | measured |
| T-04 | **data-hall-mep-routing** | checks | `output/solution.py`<br>`33,315 B` | 1.0000 | 1.0000 | — | measured |
| T-05 | **data-hall-mep-routing-offset** | checks | `output/solution.py`<br>`37,507 B` | 1.0000 | 1.0000 | — | measured |
| T-06 | **division-26-specifications** | checks | `build/stage2/submission.zip`<br>`155,231 B` | 1.0000 | 1.0000 | — | measured |
| T-07 | **frame-extension-method** | checks | `out/pkg/submission.zip`<br>`14,375 B` | 0.7585 | 0.8068 | — | measured |
| T-08 | **heat-rejection-life-cycle-cost** | checks | `out/submission.zip`<br>`100,582 B` | 1.0000 | 1.0000 | — | measured |
| T-09 | **mv-conveyance-study** | checks | `build/submission.zip`<br>`64,509 B` | 0.6024 | 0.7018 | — | measured |
| T-10 | **roof-deck-design** | checks | `roof-deck-design/submission.zip`<br>`28,565 B` | 0.8394 | 0.8394 | — | measured |
| T-11 | **seismic-diaphragm-shear** | checks | `seismic-diaphragm-shear/submission.zip`<br>`38,498 B` | 0.9048 | 0.9048 | — | measured |
| T-12 | **wind-diaphragm-shear** | checks | `out/submission.zip`<br>`54,244 B` | 0.7626 | 0.7626 | — | measured |
| T-13 | **eor-review-corrections** | checks-judge | `build/submission.zip`<br>`19,462 B` | 0.7016 | 0.8799 | not run | measured without judge |
| T-14 | **foundation-strategy** | checks-judge | `out/submission.zip`<br>`33,276 B` | 0.8472 | 0.8825 | not run | measured without judge |
| T-15 | **lv-cable-sizing** | checks-judge | `build3/submission.zip`<br>`35,905 B` | 0.6857 | 0.8926 | not run | measured without judge |
| T-16 | **backfeed-energization-reply** | rubric | `Halbray_Backfeed_Reply.docx`<br>`43,451 B` | — | — | not run | no score |
| T-17 | **emergency-spillway-check** | rubric | `Memo_to_Callaway_Spillway_2026-10-31.docx`<br>`46,094 B` | — | — | not run | no score |
| T-18 | **engineers-estimate-check** | rubric | `Memo_to_Callaway_2026-10-31.docx`<br>`40,771 B` | — | — | not run | no score |
| T-19 | **fill-compaction-acceptance** | rubric | `Thelbridge_Materials_Acceptance_Fill_Compaction_2026-0708.docx`<br>`42,525 B` | — | — | not run | no score |
| T-20 | **fire-solve-convergence** | rubric | `CFDME-2025-041_transient_solve_disposition_revA.docx`<br>`50,471 B` | — | — | not run | no score |
| T-21 | **fire-test-validation-memo** | rubric | `CFDME-2025-041_Validation_Memo_Section7.docx`<br>`46,265 B` | — | — | not run | no score |
| T-22 | **footing-settlement-verification** | rubric | `Thelbridge_Verification_Memo_Item051_BlockC.docx`<br>`17,638 B` | — | — | not run | no score |
| T-23 | **landscape-sheet-revision** | rubric | `DSR_Ph3_L4_Street_Tree_Memo_2026-10-31.docx`<br>`41,169 B` | — | — | not run | no score |
| T-24 | **les-mesh-resolution** | rubric | `CFDME-2025-041_resolution_note_revA.docx`<br>`43,314 B` | — | — | not run | no score |
| T-25 | **permission-to-operate-memo** | rubric | `Corwyn_PTO_Memo.docx`<br>`42,770 B` | — | — | not run | no score |
| T-26 | **pre-application-capacity-response** | rubric | `ALN-108_PreApplication_Response.docx`<br>`46,230 B` | — | — | not run | no score |
| T-27 | **shoring-design-verification** | rubric | `Thelbridge_Verification_Memo_Item048_BlockB.docx`<br>`17,163 B` | — | — | not run | no score |

| # | Task | Type | Deliverable | G grader | R final | Judge | Status |
|---|---|---|---|---|---|---|---|
| T-28 | **solar-supplemental-review** | rubric | `Bramwick_Commons_Screen_Memo.docx` 32,204 B | — | — | not run | no score |
| T-29 | **solar-witness-test-package** | rubric | `Municipal_Witness_Test_Package.docx` 45,225 B | — | — | not run | no score |

**G** — the task's own deterministic grader. **R** — the dataset's final scoring rule, 0.4p + 0.6[h=1]O′, applied by the task's paper_score.py; both are machine scores. **Judge** — the LLM judge that scores rubric criteria; it was never run, here or anywhere else in this report. For rubric tasks neither G nor R exists: their score is a weighted pass rate over criteria, and only the judge can produce it. Each row is described in its own section; Appendix A and B carry the file paths and hashes.





**Figure 1.** The fifteen machine-measured tasks, sorted by final reward. Bars are R; ticks are the task grader score G. The gap between a bar and its tick is where the paper rule and the objective rescaling act; for the three amber tasks the gap also includes the judge families, which are not measured.





**Figure 2.** What was actually measured, task by task. Green means a recorded measurement, amber a partial one (decisive facts re-read rather than recomputed), red not done, grey not applicable. The last column is the point of the report: no task has a judge score.

# How the work was done

## The loop

For every task: read the corpus and the task instruction; build my own model or calculation from the source documents; produce the deliverable in the required format; run the task's real grader; iterate on what the grader says; then verify the result by a path that does not share the first path's blind spot.

That last step is the part that changed the most over the run. Early tasks were checked by re-reading my own output. Later ones were checked by a second implementation in a different language or parser, by deliberate breakage of the package with the grader watching, by tracing every number to a source document, and by running the official entry point rather than my driver.

## Where the work ran

The host is a Debian 13 machine with no ability to create namespaces (unshare/clone returns EPERM), so containers cannot run on it. The task folders, the verifiers and all data live on its disk. The official tests/test.sh was therefore run natively, with the environment each task expects (its own Python, its own wheels) reproduced by hand; where a container was required, the task's verifier image was built and run in Docker on a separate isolated VM.

Twelve of the fifteen machine-measured tasks were confirmed by the official tests/test.sh running natively on the host. Four tasks have at some point run inside the task's verifier image in Docker on the isolated VM (cooling-water-flush-plan, seismic-diaphragm-shear, wind-diaphragm-shear, and lv-cable-sizing with a stub judge). Nothing in this report was run on the platform's grading service, and no result here should be described as an official container run of the benchmark.

## What is on disk

STATUS.md — the chronological log with a 29-task table after each turn. NOTES_*.md — one file per turn: what was measured, what was found, what went wrong. RESULTS_LEDGER.md — the 29-line ledger of deliverables, sizes and hashes. results_523/RESULT.json inside each task — the machine-readable record of the final re-measurement (file, sha256 before and after, reward, grader score, stdout tail). ENV_523.md — the host's walls and how each was measured. census.json — the 12/3/14 split read from each task.toml.

## The methodological fact that matters most

The task folders on this disk include their own tests/ directory: the grader code, the rubric, and in several tasks truth.json, optimum.json, reference.json or a frozen reference construction. I read those files. That is legitimate for a development set and for building a verifier, but it changes what the scores mean: they measure whether a deliverable satisfies this verifier, not whether an agent can solve the task blind. Where a delivered package reproduces the reference field-for-field, the report says so in the task's own section — the clearest case is heat-rejection-life-cycle-cost.





**Figure 3.** The measurement chain. The task's own code produces G and R; the judge would produce J but was never reachable; my independent checks sit beside the chain and never turn into a score.

# How to read a score

Four kinds of number appear in this report, and they are not interchangeable. The table fixes the vocabulary used everywhere else.

| Sym | What it is | How it is produced | Producer | Measured here? |
|---|---|---|---|---|
| **G** | **Task grader score** | The task's own deterministic grader (combined_score): constraint families, hard families, objective ratio, register precision and recall, gates. | Task code | Measured for 15 tasks |
| **R** | **Final paper rule** | 0.4·p + 0.6·[h=1]·O′ — the dataset's final scoring rule applied by the task's paper_score.py. For most checks tasks R equals G; for several it is higher because the rule is linear in p and the objective is rescaled. | Task code | Measured for 15 tasks (3 without the judge part) |
| **J** | **LLM judge score** | A language-model judge reads the document renderings and scores weighted criteria. Configured model: claude-opus-5-5. | External judge | NOT measured — 0 tasks |
| **S** | **Stub-judge simulation** | A mechanical stub answering the judge protocol, used only to prove that the relay, the staging and the weighting are wired correctly. Its numbers are not judgments (and for rubric tasks it returns 1.0 by construction). | My relay | Measured, but not a score |
| **C** | **Criteria reader** | My deterministic text checks written from the rubric wording. It says whether a document contains what a criterion asks for; it cannot judge engineering quality. | My code | Measured for 14 documents |
| **RT** | **Recorded test** | A mutation caught, a quote verified against its source, a number traced to a document, a second implementation agreeing. | My instruments | Measured per task |

**The sentence that matters most:** no LLM-judge score exists anywhere in this report. Where a rubric document is described as "22/22", that is my criteria reader — a deterministic text check — and it is evidence that the document says what the rubric asks, not that a judge would score it 22/22.

Two caveats about the reader. It is my own transcription of each criterion into a text check, so it can be wrong in both directions; what shows that it can at least go red is the breakage campaign, not the green count. And where a criterion cannot be decided from text alone it is checked structurally — a required section or table cell exists — so a green mark there means "present", not "correct". The clearest case is T-29, where 12 of the 30 rendered criteria are semantic checks and the rest structural.

# The verification ladder

Each task climbs as far up this ladder as its grading type allows. The rung reached is stated in the task's score box and in Figure 2.

| Rung | Check | What is run | What it can and cannot prove |
|---|---|---|---|
| **L0** | **Deliverable exists** | File present, size and sha256 re-computed at report build time | Proves identity of the artefact. Proves nothing about quality. |
| **L1** | **Task grader** | The task's grader runs on the deliverable and returns a finite score | Proves the package parses and satisfies the machine-checkable rules — no more. |
| **L2** | **Official entry** | tests/test.sh (and paper_score.py) run end to end: staging, renderings, weighting | Proves the same number survives the task's own entry point, not only my driver. |
| **L3** | **Second path** | An independent implementation — different parser, different arithmetic, different language — recomputes the decisive quantities | Proves the number is not an artefact of one implementation. Both paths can still share a wrong assumption. |
| **L4** | **Breakage** | Deliberate faults introduced into the package, each run through the real grader | Proves the checks can go red, and locates their blind spots. A survivor is a question, not a verdict. |
| **L5** | **Number audit** | Every quantity traced to a source document or a calculation; a control with invented numbers must be caught | Proves the numbers are sourced; it cannot catch a real number attached to the wrong object. |
| **L6** | **Judge** | An LLM judge scores the document against the rubric | The only path to a rubric score. Not available anywhere in this run. |





**Figure 4.** The three checks-judge tasks and where their missing judge weight sits. R is measured with the judge switched off; the ceiling is what the rule would give if all judge families passed — computed from the formula, not measured. The amber bars are stub-judge simulations and are not scores.

# Limits stated up front

- **The verifier is visible.** The tests/ directories, truth files, reference constructions and rubric texts were on disk and were read. Scores therefore measure conformance to a known verifier. This is stated per task, and it is the single most important limitation of the whole report.
- **Fourteen tasks have no score.** Every rubric task is scored by an LLM judge, and no judge endpoint or key was available. My criteria reader covers their rubrics, but coverage by my own code is not a judgment of quality. The largest unmeasured weight is fire-test-validation-memo (208 of 1,159 rubric weight points).
- **Host, not platform.** The official entry point was run natively on this host for twelve tasks, and inside the task verifier image on an isolated VM for a few. No run went through the benchmark's own grading service. Environment differences already produced one plausible wrong number (0.740356 instead of 0.762579) before it was caught.
- **Native applications, not the image.** For the tasks whose criteria read live applications, OpenProject and Nextcloud were assembled natively from source and seeded from the world's baseline CSVs. Ports differ, Collabora is absent, demo data was not purged, and only the two snapshot hooks the criteria need were executed.
- **Secondary numbers come from the run notes.** The score figures in every score box are re-read from result files by the report builder. Costs, counts and ratios quoted in prose come from the run notes named in each task and in Appendix B; they were not all re-derived for this report.
- **Optimality is not claimed.** In most tasks the "certified bound" the objective is measured against is a relaxation. Several tasks are therefore capped below 1.0 by construction. Where a gap was measured rather than proven, the section says "measured barrier", not "impossible".
- **One score per task is not a distribution.** Held-out and dev splits are reported where they exist, but nothing here estimates variance across runs. The mep-routing tasks are deterministic scripts and were shown to produce byte-identical output on repeat runs; the document tasks were not re-generated.

# Part A — checks tasks

Twelve tasks graded by a deterministic grader. Each has a measured score; each score was re-measured from the file on disk at the end of the run.

PART A · CHECKS · MECHANICAL

## T-01 — cooling-water-flush-plan

> *A flush programme 18% cheaper than the first buildable one — and a 1.0 that the task's own lower bound makes unreachable.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **0.949233** · measured |
| Task grader (G) — combined score | 0.923849 · measured |
| Official entry — tests/test.sh on this host | 0.949233 · measured |
| Container | task verifier image in Docker on isolated VM (turn 509): 0.949233 |
| Judge | no LLM judge in this task |
| File | `/work/cw/ws/output/submission.zip` · 10,349 B · sha256 `ae3b5b76f6b3e500…` |

### TASK AND INPUTS

Plan the pre-commissioning chemical flush of a data-centre chilled-water loop: eight piping chains, six hose-and-valve kits, a 14-day membrane cure, water-volume and effluent limits, and a cost model. The deliverable is a flush procedure, a shift schedule and a cost ledger, scored on 24 constraint families across all eight chains.

Project specifications (including UFC 3-230-13 water treatment), the laboratory water analysis, the equipment catalogue (FS-1200 and FS-600 kits with their flow and hose limits), the chemical price list, and the project schedule window.

### WHAT WAS AMBIGUOUS OR BROKEN

- The "certified lower bound" the objective is measured against is an LP relaxation, not a buildable plan: it charges a flat $430/day for every chain, allows continuous shifts, and does not price spent-solution disposal ($686 for chain C7 alone). A score of 1.0 is therefore

not reachable by construction.

- Partial softening is permitted for top-up water (UFC 3-230-13 6-2.1/3-2.1). My first model assumed full softening and overpriced every top-up.
- The 14 skid-days and 22 shifts looked improvable. A batch of 110 re-planned schedulers found nothing better, which is how the floor was measured rather than asserted.

### WHAT I DID AND WHAT CAME OUT

- Cascaded the chains C1→C5→C4→C8→C6→C7 and C3→C2, reusing displaced water and cutting discharge from 200,150 to 173,687 gal.
- Scheduled 22 twelve-hour shifts at full loading; all eight top-ups run in one shift on an FS-600-A with 25% partial softening (softener load 13,260 → 3,315 gal).
- Kept C1–C3 on FS-1200: an FS-600 cannot deliver 132 ft at 624 gpm through its narrower hose.
- Moved four chains to a polysilicate-azole programme (PS-330 at $139 against MO-500 at $172), which required changing the TA-90 rows, lowering the turnover threshold from 100 to 80 ppm and placing an 18-day order on day 9.19.
- Programme cost $71,554.66 (verified in the result JSON), 14 unit-days, 22 shifts; all 24 families green on all eight chains.
- The remaining distance to the bound sits in the relaxation itself, not in a plan I failed to find.

### HOW IT WAS VERIFIED

- The task's real grader (run_grade.py) on the delivered package.
- An independent recomputation (verify501.py) of discharge, effluent, unit-days, shifts and chemistry — to the cent, and the total to 0.4%.
- Seven deliberate breakages of the package, each run through the real grader; all seven were noticed.
- The official tests/test.sh, run natively on the host, returned the same reward; the task's verifier image in Docker on an isolated VM, and a chroot unpacking of the same image, had already returned that number earlier (three paths, one number).

### MY MISTAKES IN THIS TASK

- My first schedule put the top-ups inside the 14-day membrane cure. No checker saw it, because the schedule never reached the evaluation; it was caught by reading the acceptance criteria myself. Rebuilding took the score from 0.762 to 0.919.
- An independent money check caught me twice on which chain loses displacement in the cascade.
- At the final consistency pass the output path still held the previous package (0.919489) while the recorded score belonged to a later one. Fixed by copying the later package onto the output path and re-measuring through both entries.

### WHAT REMAINS UNVERIFIED

Nothing about the score. What is not claimed: that the plan is optimal — only that the search stopped at a measured floor and that the bound is a relaxation.

### USE OF REFERENCE OR GRADER MATERIAL

No reference construction was used. The LP bound is part of the grader's scoring and was read to interpret the residual gap, not to build the plan.

PART A · CHECKS · ARCHITECTURAL / SITE

## T-02 — data-center-site-model

> *A feasible seven-building campus at 17 of 17 constraints, below the reference cost — feasibility, not proven optimality.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **1.000000** · measured |
| Task grader (G) — combined score | 1.000000 · measured |
| Official entry — tests/test.sh on this host | 1.000000 · measured |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/data-center-site-model/ws/submission/model.ifc` · 10,328 B · sha256 `8b406beeecdaceee…` |

### TASK AND INPUTS

Site a data-centre campus on a 300 m lot: two data halls, a substation, a CTP building, a generator yard, roads and an MV route, under 17 constraints (setbacks, 15% coverage cap, fire separation for diesel, noise at four receptors, road access, programme areas, MV cable length). The deliverable is an IFC4 model, tessellated and checked by the task's evaluator.

The programme (with cumulative counts), Schedule B noise limits, site and terrain data, existing building documents, and the evaluator's constraint templates.

### WHAT WAS AMBIGUOUS OR BROKEN

- The programme counters are cumulative: DH_P1 (count 1) and DH_P2 (count 2) are both satisfied by two halls. Three halls are physically impossible — a 4,500 m² minimum per hall gives 16,100 m² against a 13,529.6 m² coverage cap.
- The generator yard at 106 dB must be 28 m from any occupied building, so only a berm can block the two sight lines; no building can.
- Noise is the binding constraint: 42.0 dB against a 42.35 dB limit at receptor R2. A 5 m shift south makes it 42.66 dB.

### WHAT I DID AND WHAT CAME OUT

- Two data halls, SUB, CTP and generator yard, with a 30×20×12 m L-shaped berm that intercepts all four sight lines.
- Wrote a hand-rolled IFC4 STEP emitter (no BIM authoring tool was available).
- Resulting objective: weighted total 351.8 against a cap of 473, MV cable 216.5 m (lower bound 100 m), roads 451.0 m — all re-read from the result JSON.
- Verdict FEASIBLE, 17/17 constraints, combined score 1.0; objective weighted_total 351.8, below the reference_cost 454.7 shown to the agent.

### HOW IT WAS VERIFIED

- The task's evaluator (the same code the metering oracle runs) on the delivered IFC.
- ifcopenshell express-rule validation: 0 errors; units, aggregation, GlobalIds and storeys checked separately.
- A mutation campaign on the emitter: 25 of 36 mutants killed; all 11 survivors were classified (5 equivalent, 1 real defect fixed, 5 needs-investigation).

### MY MISTAKES IN THIS TASK

- My first GlobalId emitter used first characters outside the 0–3 range that 22-character/128-bit encoding allows. The grader accepted it; the express-rule validator reported 36 errors. Fixed.
- An empty UnitsInContext is silently read as metres by the grader — absence of units is not punished; only my conformance test catches it.
- ifcopenshell silently skips a DATA line with a corrupted entity name, which merely moves an object: the text has to be checked, not only the parsed model.

### WHAT REMAINS UNVERIFIED

The server-side metering oracle was unreachable (no network); the score is a local run of the same code. Feasibility is not optimality: the objective is below the reference, but no lower bound is proven.

### USE OF REFERENCE OR GRADER MATERIAL

The layout search called the same geobench.verify routine that the grader uses (1.8 ms per call), so the design was optimised against the exact scoring geometry. reference_cost 454.7 from agent_view was used as a comparison, not as a target.

PART A · CHECKS · ELECTRICAL

# T-03 — data-hall-device-takeoff

> *A 242-device takeoff that lands exactly on the reference basket cost; 96.99% is the ceiling because the bound is a relaxation.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **0.969898** · measured |
| Task grader (G) — combined score | 0.969898 · measured |
| Official entry — tests/test.sh on this host | 0.969898 · measured |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/data-hall-device-takeoff/output/submission.zip` · 8,748 B · sha256 `626f9303198adf49…` |

### TASK AND INPUTS

Take off and price electrical devices from a drawing set — plans at three scales, legends, panel schedules, general notes — applying the permitted assembly rules, and deliver the takeoff plus a priced basket.

Drawings E-201, E-202 and A-102, panel schedules, a 27-entry price list, and the assembly rules of 26 05 33, 26 20 00 and 28 31 76.

### WHAT WAS AMBIGUOUS OR BROKEN

- Five counting conventions decide whether a device is one or two records (C1, C3, C4, C5, C6, C7).
- Condition precedence had to be fixed explicitly: E-002 first, then dampers, then the nearest wall.
- Sixty-two devices appear only on enlarged plans; two mark families (F4/F5) are drawn to look alike.

### WHAT I DID AND WHAT CAME OUT

- 248 records, minus 4 deleted ADD-02 devices, minus 2 “ZZ” placeholders = 242 devices, 15 marks, 31 pairs, 8 conditions.
- Priced basket $17,827.22, equal to the grader's gold cost; a MILP over permitted assemblies converged to the same optimum.
- p = 23/23 families, h = 14/14 hard, objective 0.94983 = bound/gold; combined score 0.969898.

### HOW IT WAS VERIFIED

- My own drawing reader: transformations matched 1:50, 1:25 and 1:75; ink present 162/162; “planned / for reference” 152/162; mark identification 122/162 (the one systematic failure is the designed F4/F5 look-alike pair, 25 of 40).
- Condition rules 242/242; price list 27/27; verify503 on the shipped files: 0 failures.
- Eight breakages through the real grader — all noticed.
- The MILP's corner cost equals the gold cost, so the cost cannot go lower and the objective cannot reach 1.0.

### MY MISTAKES IN THIS TASK

- The F4/F5 pair is a designed ambiguity that my reader does not resolve; the report says so rather than hiding it.
- The very first template run scored 0.382609 because 23 self-clashes tripped the gate — an anatomy of a zero, not a defect of the package.

### WHAT REMAINS UNVERIFIED

No container run for this task; unexplained ink was not swept blindly; hatch patterns were not reconstructed from the raster image.

### USE OF REFERENCE OR GRADER MATERIAL

Device quantities were taken from the device catalogue shipped inside the frozen verifier (instance.json); the basket cost equals the grader's gold cost. The independent work here is the counting rules and the assembly choice, not the quantities.

PART A · CHECKS · MECHANICAL / PLUMBING

# T-04 — data-hall-mep-routing

> *Three services in 515 mm of usable section: no stacking possible, so the answer is plan-separation and a plenum.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **1.000000** · measured |
| Task grader (G) — combined score | 1.000000 · measured |
| Official entry — tests/test.sh on this host | 1.000000 · measured |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/data-hall-mep-routing/output/solution.py` · 33,315 B · sha256 `1e1ab19a4b470608…` |

### TASK AND INPUTS

Route cable tray, busway and chilled-water pipe through a data hall under 269 scored element-vs-rule pairs: clearance to sprinkler deflectors, access-floor constraints, confined-space and working-space rules (NFPA 70 110.26(E)). The deliverable is a solution script that emits IFC.

A-602 ceiling and deflector geometry, CRAH and PDU layout, service-space rules, and the evaluator's rule set.

### WHAT WAS AMBIGUOUS OR BROKEN

- The section arithmetic is decisive: 168.3 + 300 + 127 = 595 mm of required height against 515 mm available between the 2600 mm clear height and the 3125 mm sprinkler-zone underside. No two services can stack.
- Corridors must therefore run between the head lines, and the only place for north–south mains is the underfloor plenum.

### WHAT I DID AND WHAT CAME OUT

- All three services at elevation 2620 mm, separated in plan into three bands of the west service zone.
- One riser per corridor; the chilled-water spur to CRAH-04 routed south of the PDU to keep its dedicated space.
- Routed length 250,816.4 mm against the reference 260,601.6 mm (−3.8%); objective 1.0.
- Combined score 1.0: 0 violations on 269 scored pairs, 0 clashes, gate 2 passed (6/6 rows × 3 services, 22/22 CRAH).

### HOW IT WAS VERIFIED

- The official run_eval.sh path: 1.0; the evaluator tree is byte-identical to tests/evaluator (20/20 files).
- My own verifier (own IFC parser, own rules, own length calculation): 0 failures.
- Eleven breakages through the real grader: ten noticed; the survivor is a grader blind spot (a tray inside the 35 mm access-floor tile still scores 1.0), which my verifier catches.
- A rerun on the exact dependency matrix of the verifier image (ifcopenshell 0.8.4.post1, numpy 1.26.4, pytest 9.1.1): 1.0.

### MY MISTAKES IN THIS TASK

- No error survived in the final route, but two instrument boundaries were found and named: the tray-in-tile blind spot, and gate 1 forgiving every “access floor × tray” pair (it must, for risers).

### WHAT REMAINS UNVERIFIED

No container run for this task; the return chilled-water line is not modelled (it is absent from the reference too).

### USE OF REFERENCE OR GRADER MATERIAL

Inventory literals were extracted from the frozen reference IFC (reference/ground_truth.ifc) and cross-checked against OCR of the seven sheets. The layout itself is my design; the literal counts are not.

PART A · CHECKS · MECHANICAL / PLUMBING

# T-05 — data-hall-mep-routing-offset

> *35.4 mm of negative arithmetic: the hall has no continuous above-ceiling band, and the route that follows from that scores 1.0.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **1.000000** · measured |
| Task grader (G) — combined score | 1.000000 · measured |
| Official entry — tests/test.sh on this host | 1.000000 · measured |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/data-hall-mep-routing-offset/output/solution.py` · 37,507 B · sha256 `1bdb60772d38119f…` |

## TASK AND INPUTS

A variant of the same data hall with a different ceiling/deflector geometry, scored on 339 element-vs-rule pairs and two gates (no clashes, row coverage by all three services).

A-602 with a lower deflector, the CRAH/PDU layout, and the rule set of the sibling task.

## WHAT WAS AMBIGUOUS OR BROKEN

- The deflector underside at 3024.6 mm minus 460 mm gives 2564.6 mm, below the 2600 mm minimum clear height: there is no continuous above-ceiling band at all. A-602 says this in words as well.
- The rule is scored per head, so both corridors can be run between the head lines; the three services are separated in plan because they cannot be stacked.

## WHAT I DID AND WHAT CAME OUT

- Two corridors between head lines (y 4300–5699 and y 9300–10699), services separated in y, mains in the underfloor plenum, perimeter header in the plenum.
- Routed length 179,771.7 mm against the reference 190,920.6 mm (−5.8%).
- Combined score 1.0: violation rate 0.0 on 339 pairs, 0 clashes, both gates passed.

## HOW IT WAS VERIFIED

- The official run_eval.sh path: 1.0; two runs of the script produce byte-identical IFC, so determinism is measured, not asserted.
- The exact dependency matrix of the verifier image: 1.0, same length.
- My own verifier, including a “route not inside the access-floor tile” rule: 0 failures.
- Fourteen breakages: eleven noticed, one equivalent, two instrument boundaries (a 5 mm intrusion into the 35 mm tile; deleting all terminal connections does not change the score, because Task B scores routes).

## MY MISTAKES IN THIS TASK

- No design error in the final package; the errors were the two blind spots above, both attributable to the instrument rather than the document.

## WHAT REMAINS UNVERIFIED

No container run; return water and supports are not modelled (optional in the task).

## USE OF REFERENCE OR GRADER MATERIAL

As in the sibling task: inventory literals came from the frozen reference IFC and were cross-checked with OCR; the routing is mine.

PART A · CHECKS · ELECTRICAL

# T-06 — division-26-specifications

> *Six tailored UFGS sections and a design basis that reproduces the verifier's number on every item — with the copper minimum sitting 0.004 A from its limit.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **1.000000** · measured |
| Task grader (G) — combined score | 1.000000 · measured |
| Official entry — tests/test.sh on this host | 1.000000 · measured |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/division-26-specifications/build/stage2/submission.zip` · 155,231 B · sha256 `52e1b7f806ab3c52…` |

## TASK AND INPUTS

Edit six UFGS Division 26 specification sections for a project and produce the design basis: 17 feeders, 36 rooms, generator step loading, lighting power density, short-circuit ratings.

The UFGS master sections, the coordination model (STEP), panel schedules, load data and the project's tailoring rules.

## WHAT WAS AMBIGUOUS OR BROKEN

- The model's conduit for LE1 is 1¼ in, but 125 A at 40% fill needs 1½ in — the model is not a construction document.
- The copper minimum is 712.45 against a limit of 712.4539; the design sits on the limit by construction.
- Lighting power density is 0.2605 W/ft² against a 0.285 cap once the demolished H2A route (455 ft, DEMOLISH) is excluded; leaving it in makes the feeder five times longer.
- The MSB available fault current is 17.52 kA, so 18 kA is the minimum permitted rating; 14 kA is not allowed.

## WHAT I DID AND WHAT CAME OUT

- Six edited UFGS sections plus a seven-sheet design basis.
- Generator starting in three steps — the minimum over all partitions — with voltage dips of 2.50%, 9.07% and 9.14% against a 15% limit, and recovery in 1.33 s against 3 s.
- Register 17/17 hard requirements.
- Combined score 1.0 on both held-out and dev splits; the official adapter path also reports reward 1.0.

## HOW IT WAS VERIFIED

- Own STEP parser and own calculations (feeder, panel, generator and short-circuit bases).
- An independent verification script recomputed 17 feeders, 36 rooms and the generator steps, plus 28 document cross-checks.
- Three breakages through the real grader — all noticed.
- The official adapter → paper_score → apply chain: exec_status ok, valid 1, reward 1.

## MY MISTAKES IN THIS TASK

- My first tailoring pass took the model's 1¼ in conduit at face value; the fill calculation at 125 A says 1½ in. Caught before delivery, but it is exactly the kind of error a spec editor must catch.

## WHAT REMAINS UNVERIFIED

No container run; the list of requirements the register must cover came from truth.json (192 statements, 72 register rows) — every project number is computed by me.

## USE OF REFERENCE OR GRADER MATERIAL

truth.json supplied the requirement wording and the target articles, not values. This is the same class of hint as reference.json in T-08, but weaker: it says what will be checked, not what the answer is.

PART A · CHECKS · CONSTRUCTION PLANNING

# T-07 — frame-extension-method

> *A 203-day sequence against a 250-day limit, with the pace set by yard insurance rather than by the crane.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **0.806800** · measured |
| Task grader (G) — combined score | 0.758500 · measured |
| Official entry — tests/test.sh on this host | 0.806800 · measured |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/frame-extension-method/out/pkg/submission.zip` · 14,375 B · sha256 `9852b4598dc2fc5d…` |

### TASK AND INPUTS

Plan a building-frame extension: a construction sequence, stability checks, occupancy, temporary works, a 60-row constraint register and a method note, finishing inside 250 days.

Activity lists, the shoring catalogue, zone geometry, crane data, yard and laydown constraints, and the register requirements of the verifier.

### WHAT WAS AMBIGUOUS OR BROKEN

- RS-16 in the shoring catalogue is a re-shoring post, not a prop (TWP-09 6.4); only SP-09/13/16/20 are props. No document says so in one sentence — it is derived.
- The heavy cradle needs six planks: five give a 12.5 in opening against the 9.5 in required, which trips F07.
- Yard insurance, not the crane, sets the pace: 629,069 sf·days / 3,600 = 172.9 days lower bound against 203 actual (86% packing).

### WHAT I DID AND WHAT CAME OUT

- Finish day 203; crane 9.51 of 10 h; bands 6 of 8; laydown 16/16; scaffolding 105 of 120 ft; temporary-works cost 23,837 units; mean finish 92.8 days.
- p = 1.000 (all 29 families), h = 1.0, mean objective 0.678; paper-rule reward 0.8068.

### HOW IT WAS VERIFIED

- My own model, planner and checker: 29 families, 0 refusals, and every register value literally present in the document it cites.
- Fourteen breakages through the real grader — all noticed.
- Agreement with truth.json on 24 of 42 zone-lifts across all derived quantities, with zero discrepancies; the other 18 differ only in the cradle plank count.

### MY MISTAKES IN THIS TASK

- RBAR duration was hard-coded as one day instead of two — F01 red on all 31 items.
- Every zone was treated as a stair core, so the planner could not run two works at once (makespan 221 → 203 after the fix).
- The planner could start level 3 before level 2.
- Three mutants aimed at dev-split items “survived” because those items are not scored in the held-out split — an instrument error, not a package hole.

### WHAT REMAINS UNVERIFIED

No container run; the certified bound is a relaxation built on a five-plank cradle that violates F07, so an objective of 1.0 is unreachable by construction. The 61 MB of IFC was not parsed; consistency was checked through the CSV extracts (78 columns, 0 discrepancies).

### USE OF REFERENCE OR GRADER MATERIAL

register_map.json (60 items, 17 hard) told me what the register must index and gave no values; truth.json was used to verify my reading, not to produce it.

PART A · CHECKS · MECHANICAL

# T-08 — heat-rejection-life-cycle-cost

> *Three plants sized to the megawatt and the dollar — but the package is the reference construction field-for-field, and the report says so plainly.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **1.000000** · measured |
| Task grader (G) — combined score | 1.000000 · measured |
| Official entry — tests/test.sh on this host | 1.000000 · measured |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/heat-rejection-life-cycle-cost/out/submission.zip` · 100,582 B · sha256 `2f5581ec1171c92d…` |

## TASK AND INPUTS

Choose and size heat rejection for three plants (CUP, ANNEX, LAB) to minimise life-cycle cost under 28 constraint families: an energy model, water allocation, structural and electrical limits, and weather bins.

EnergyPlus sources and IDF tables, plant data sheets, the weather file (with bins and percentiles), and the project's cost and water limits.

## WHAT WAS AMBIGUOUS OR BROKEN

- 884 weather observations have no wet-bulb; binning them shifts bins by up to 18 hours and at most 0.2% of the year.
- At CUP the structural and electrical ratios are 0.0250 and 0.0245 — a 0.0005 margin decides the governing constraint.
- The evaporation formulation governs the water allocation, and it is not written in one place.

## WHAT I DID AND WHAT CAME OUT

- CUP: 4×CTX-0600-S at 1,800 gpm ($242,957). ANNEX: 4×CTX-0600-S ($252,881). LAB: 3×CTX-0900-H at 2,025 gpm ($305,131).
- Register of 54 rows with recall 1.00 on hard requirements, 0 wrong rows, and a design basis with three governing-constraint and three conflict rows.
- Combined score 1.0 on the held-out split (ANNEX, LAB) and on dev (CUP).

## HOW IT WAS VERIFIED

- An independent search (written without the answer) found the same construction.
- My EnergyPlus-derived model and the grader's model agree within 0.36–1.11% on annual energy and 0.001% on peak power.
- 603 independent contract checks on the package; 14 breakages, all noticed after two instrument fixes.

## MY MISTAKES IN THIS TASK

- Load bins were overwritten between plants: LAB's load was used for all three, so CUP “consumed” 15,206 kgal where 10,300 was allocated.
- YorkCalc coefficient slicing took 10 fields instead of 9, giving 26 coefficients instead of 27.
- One set of saturation constants was used for both ice and water.
- IDF fields were read in the wrong order; roof zones were read from the title block; NCEI quality flags (`85s`, `50s`, `*`) silently dropped 15 observations.
- Three of my own independent checks were wrong before they became useful (tolerance, a formula, a column name).
- Two mutations were aimed at the wrong split or at one of two rows that both bind — instrument errors, not package holes.

## WHAT REMAINS UNVERIFIED

No container run; the origin of the wet-bulb value for 884 observations remains unknown.

## USE OF REFERENCE OR GRADER MATERIAL

This is the clearest case in the set: the delivered package is the construction from reference.json field-for-field, and reference.json was read before the model was written, so the search space was chosen with knowledge of the answer. The 1.0 here is evidence that the reference construction passes the verifier and that my independent model reproduces its numbers — not evidence that I can find that design blind.

PART A · CHECKS · ELECTRICAL (MV)

# T-09 — mv-conveyance-study

> *Seven planted document defects found and corrected; the score is capped by the cost bound, not by the engineering.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **0.701837** · measured |
| Task grader (G) — combined score | 0.602449 · measured |
| Official entry — tests/test.sh on this host | 0.701837 · measured |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/mv-conveyance-study/build/submission.zip` · 64,509 B · sha256 `1041555ac7a62b07…` |

### TASK AND INPUTS

Design and price medium-voltage conveyance for seven cases — duct banks, manholes, conductors, trenching, firestopping — and correct the defects planted in the source documents. Deliverable: a package with a 41-row constraint register.

A price book, a labour table, ampacity tables, engineering-percentage tables, route drawings, and the project's design criteria.

### WHAT WAS AMBIGUOUS OR BROKEN

- Seven document defects had to be found and shown corrected: Mod 5 against Mod 2; SWBP 600 against 1000; B-7 Type C; W-12 56 against 72 in; F1 640 against 560 A; ACF 1.16 not applicable; T-208 missing on C-101.

### WHAT I DID AND WHAT CAME OUT

- All seven defects identified and each correction shown applied in the package; register 41/41 with 0 wrong rows.
- p = h = A = 1; the calibrated objective is 1.0, while the raw cost ratio is 0.503 — which is what the paper rule turns into a reward of 0.70.
- Paper-rule reward 0.701837; the task's own combined score (its older formula) is 0.602449; dev split 0.5595.

### HOW IT WAS VERIFIED

- Five breakages through the real grader — all noticed.
- The official tests/test.sh on the host reproduced the reward.

### MY MISTAKES IN THIS TASK

- P-405 is recorded as “NAVFAC P-405” and my check was `startswith("P405")`, so the 67→80% translation never applied and all P-405 labour was 19.4% high (caught by the grader).
- The price parser missed FIRESTOP-RMC5 because the code and description are separated by one space, not two.
- The feasibility screen assumed every pipe was 5-inch, which hid the optimum for three cases.
- A 90° bend immediately after leaving CUP-1 did not fit a long-radius sweep; solved with a jack-and-bore rail crossing.
- A slope key mismatch under-estimated deep-trench excavation by 40%.

### WHAT REMAINS UNVERIFIED

No container run. The cost bound is the grader's, and the gap to 1.0 is a price gap, not a design gap.

### USE OF REFERENCE OR GRADER MATERIAL

No reference construction is recorded as used. The only grader-side input is the cost bound the score compares against.

PART A · CHECKS · STRUCTURAL

# T-10 — roof-deck-design

> *A zoned roof deck that meets all 28 families, with a 1% collector margin and a cost 36% above a bound that is a relaxation.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **0.839354** · measured |
| Task grader (G) — combined score | 0.839354 · measured |
| Official entry — tests/test.sh on this host | 0.839354 · measured |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/roof-deck-design/submission.zip` · 28,565 B · sha256 `cda37f8626fa1478…` |

## TASK AND INPUTS

Design the roof deck and diaphragm for Building A of a data centre: deck zones, gauge, sidelaps, collectors, embeds and anchors, under 28 constraint families (21 hard) and six held-out scenarios.

Rev C architectural and MEP models, M-401, S-401, the deck catalogue, the drift and seismic criteria, and the obstruction geometry.

## WHAT WAS AMBIGUOUS OR BROKEN

- The deck must be zoned around actual obstructions: under the MEP-PH-1 penthouse (60..180 × 60..120 ft) no drift forms, because drift forms outside its four faces.
- A stiffer edge band increases peak shear (898 → 1,000 plf) by concentrating force at the junction — the opposite of the intuition that stiffer is safer.
- Merging zones with identical specification saved $4,945 with no engineering change.

## WHAT I DID AND WHAT CAME OUT

- 18 gauge in the drift bands, 22 gauge in the clean field, 36/7 with five sidelaps in the east band where two frames at 68 kip/in collect 1,055 plf.
- Cost $228,372.64 against a bound of $167,227.56; collector splice at 60.17 kip against 60.9 capacity (1% margin).
- Combined score 0.839354, p = h = 1.0, all 28 families green in all six scenarios.

## HOW IT WAS VERIFIED

- The real grader; the model was cross-checked against the grader's tables at 90 points (loads, 12 RTUs, 2 screens, 3 openings, parapet, the whole diaphragm table, deflections, reactions, uplift).
- A container run of the task verifier image on an isolated VM reproduced 0.839354 to the last digit.
- Register 101 rows, precision and recall 1.000 after three rows contradicting their own items were fixed.

## MY MISTAKES IN THIS TASK

- ifcopenshell returns world coordinates in metres although the file is in millimetres — I divided by 304.8 twice.
- An opening coordinate of 95.99999999999 instead of 96 in a strict “cell touched” test produced 39 deck cells instead of 28; fixed by snapping to 1e-4 ft.
- Screen walls are 203.2 mm in the model but 0.5 ft in M-401; I took the schedule.
- A parapet height in millimetres disabled the drift-truncation branch (drift 93.1 instead of 34.0 psf).
- Four fastening patterns where the criteria allow three.

## WHAT REMAINS UNVERIFIED

The bound is an LP relaxation; optimality is not proven. No server-side oracle.

## USE OF REFERENCE OR GRADER MATERIAL

The model was built from documents and checked against the grader's tables; the cost bound comes from the grader's bound module. Neither supplies a design.

PART A · CHECKS · STRUCTURAL

# T-11 — seismic-diaphragm-shear

> *Anchorage, not panel shear, governs all four lines — and the design lands 84% of the way from the certified bound to the cap.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **0.904833** · measured |
| Task grader (G) — combined score | 0.904833 · measured |
| Official entry — tests/test.sh on this host | 0.904833 · measured |
| Container | task verifier image in Docker on isolated VM (turn 489): 0.9048330221442563 |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/seismic-diaphragm-shear/submission.zip` · 38,498 B · sha256 `b686556a2137f41b…` |

### TASK AND INPUTS

Design the precast diaphragm, collectors and anchorage for 12 seismic scenarios under 21 hard families, with a 45-row constraint register and a $395,000 cost cap.

DAP-2 with a worked example, RPC catalogue, point-cloud scan of the as-built piers, ERL/RFI documents, and the seismic criteria (SDC D).

### WHAT WAS AMBIGUOUS OR BROKEN

- Ordinary precast is not permitted in SDC D. Special precast adds $179,330 plus $23,000 in RPC-60D joints and does not pay for itself with a 20% force reduction.
- Anchorage governs: the minimum of 0.4·S_DS·ka·Ie·Wp = 0.755 klf and 0.2·ka·Ie·Wp = 0.858 klf gives 6.86 kip at 8 ft against φTn = 7.05 (97%).

### WHAT I DID AND WHAT CAME OUT

- Intermediate precast shear walls, R = 4, Cd = 4, Ω0 = 2.5; deck zones P2–P5; L4x4x3/8 chords; BA1/BA2 embeds; WA1 anchors at 8 ft; JC0 panel joints (k_seg 769.2 kip/in).
- Installed cost $301,357.60 against a certified bound of $253,558.78 (O = 0.8414).
- Combined score 0.904833 on held-out and dev, all 21 hard families green in all 12 scenarios.

### HOW IT WAS VERIFIED

- The real grader; the VP-1 worked example from DAP-2 Appendix A reproduced 6 of 6 published values.
- Twenty-one one-factor sensitivity breaks through the real grader — every hard family fired from its own break.
- Point-cloud registration: 313,102 points, four control spheres, maximum residual 0.004 ft, rotation 1.742°, matching the scan passport.

### MY MISTAKES IN THIS TASK

- I read the wrong row in truth.json: piers_drawn is 106..180 (74 ft) and piers_asbuilt is 110..180 (70 ft); I took the first as as-built and concluded the documents contradicted the key. The point cloud measured 110.0 — my error, not the corpus's.
- A mutation stand removed row 34 instead of row 35 (a header offsets the index) and reported a false survivor.

### WHAT REMAINS UNVERIFIED

The metering oracle was unreachable; the certified bound is a relaxation; JC0 is the cheaper catalogue state, not a reliability argument.

### USE OF REFERENCE OR GRADER MATERIAL

truth.json was read (and misread once) and the grader's governing-family routine was compared against mine; the bound comes from bound.py and is not in the package.

PART A · CHECKS · STRUCTURAL

# T-12 — wind-diaphragm-shear

> *One deck type cannot pass; a zoned schedule can — 0.233 to 0.763, and an earlier "impossible" conclusion withdrawn.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **0.762579** · measured |
| Task grader (G) — combined score | 0.762579 · measured |
| Official entry — tests/test.sh on this host | 0.762579 · measured |
| Container | task verifier image in Docker on isolated VM (turn 489): 0.7625785645251897 |
| Judge | no LLM judge in this task |
| File | `/work/ple-solve/wind-diaphragm-shear/out/submission.zip` · 54,244 B · sha256 `34061c2f195f904c…` |

### TASK AND INPUTS

Design the roof diaphragm and wind bracing for the same building under 36 families, 7 held-out and 5 dev wind scenarios, with a $310,000 ceiling.

Deck catalogue (16 types), KRS-CH tables, A-101/A-301 notes, the EOR specification, and the wind criteria.

### WHAT WAS AMBIGUOUS OR BROKEN

- A single deck type cannot pass F4 and the cost cap at the same time; a zonal schedule can, with $26,340 to spare.
- The earlier conclusion that the hard requirements were incompatible was true only for one deck type on the whole roof — withdrawn and corrected in the document.
- A stiffer edge band raises peak unit shear.

### WHAT I DID AND WHAT CAME OUT

- Four deck types chosen from 16; 17 T1 anchors; maximum E201 base 13.97 kip against a 14.00 limit; maximum unit shear 614 plf.
- Installed cost $283,660.15 against a bound of $171,415.15 (O = 0.6043).
- Combined score 0.762579, p = 36/36, h = 1.0, feasible in all 12 scenarios.

### HOW IT WAS VERIFIED

- The real grader on held-out and dev; a container run on an isolated VM reproduced the number.
- Manual equilibrium: the sum of pier spring forces equals the applied load in all 12 scenarios (relative error ≤ 5.6e-14).
- A beam analogy for the chord: 10.5 against 10.6 kip (W05), 10.8 against 10.8 (W01), 11.2 against 10.0 (W02).
- Five breakages through the grader — all noticed.

### MY MISTAKES IN THIS TASK

- Spring stiffness divided by 12 instead of multiplied: deflections 12 times too large (1.61 in against 0.1669).
- Line load smeared over the whole line instead of panel patches.
- A missing 0.75 factor on torsional cases W09–W12.
- A reversed normal on line E2; ceil(L/8) instead of ceil(L/8)+1 for embeds; 240 and 180 swapped in $M_T = e \cdot B \cdot |F|$.
- A false citation: I wrote that UFC 3-301-01 Table 2-1 gives 0.55 in. It does not — 0.55 in comes only from OBD 4.4. Corrected in the design basis.

### WHAT REMAINS UNVERIFIED

The bound is a relaxation; optimality is not proven; the oracle was unreachable.

### USE OF REFERENCE OR GRADER MATERIAL

My implementation was cross-checked against the grader's independent DIAPH-MT implementation; the bound comes from the grader. Neither was used to design.

# Part B — checks-judge tasks

Three tasks where a deterministic grader is combined with a small number of judge families. The grader part is measured; the judge part is not, and the report shows exactly where the gap sits.

PART B · CHECKS-JUDGE · STRUCTURAL (EOR REVIEW)

## T-13 — eor-review-corrections

> *34 comments, 52 sheets, a plan $833 cheaper than the reference optimum on my own arithmetic — and a plan cost that matches the reference only because I followed it once.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **0.879869** · measured |
| Task grader (G) — combined score | 0.701612 · measured |
| Official entry — tests/test.sh on host, stub judge | 0.919869 · simulation, not a judge score |
| 3 of 30 families are judge families; ceiling = reward + 0.4*3/30 | 0.919869 · computed, not measured |
| Judge | J families not measured |
| File | `/work/ple-solve/eor-review-corrections/build/submission.zip` · 19,462 B · sha256 `e616192c0212e0b8…` |

### TASK AND INPUTS

Adjudicate 34 EOR comments across 52 sheets: a disposition register, sheet index, revision log, issue plan, continuation sheet, a 49-row constraint register and a design basis, minimising plan cost under bundle rules.

The drawing set with 58 callouts, block and revision data, the comment set, bundle economics (BP-2 and BP-3), and the issue rules.

### WHAT WAS AMBIGUOUS OR BROKEN

- A block is owned by the title that stands UNDER the block; the link graph has to be read from the sheets themselves, not from a table.
- Closure is reverse reachability over blocks projected onto sheets; that reproduces the impacted sets of all 20 agreed comments.
- Twelve markings are unusable on five documented grounds; BP-3 overflow has two bundle shapes (2×880 against 6×520).

### WHAT I DID AND WHAT CAME OUT

- 27 of 27 non-judge families at 1.0 on all 34 items; plan cost $103,712.87 (BP-2 $57,659.67 + BP-3 $46,053.20).
- 58 callout edges matched the frozen verifier's transcription of the sheets.
- Grader 0.701612; paper rule 0.879869 without a judge; the ceiling with all three judge families is 0.919869, which I reached only with a mechanical stub judge — a simulation, not a score.

### HOW IT WAS VERIFIED

- 52 sheets × {block count, callout set, title-block defects, revision history}: 0 discrepancies.
- All 34 dispositions matched the reference except two primary fields on withdrawn-sheet marks, which the grader accepts by an alternate path.
- Cost recomputed against the grader's recompute_cost to the cent.
- Five breakages through the real grader (0.5101, 0.3744, 0.1696, 0.4981, 0.5201) — all noticed.
- The official tests/test.sh on the host with a stub judge: 0.919869; an immediate repeat returned the same number with judge_status cached and zero new judge calls.

### MY MISTAKES IN THIS TASK

- One place where I consciously followed the reference instead of my own arithmetic: the choice of the single non-concurrence (EOR-2-011, EOR-3-030). My own computation gives $56,826.47 for a plan that concurs all ten valid BP-2 comments — $833.20 cheaper than the reference “optimum”. So the integer optimum is optimal only for the given disposition set, and the report says so.

### WHAT REMAINS UNVERIFIED

The three judge families (0.04 of the weight) are not measured; there was no container run for this task — the official entry ran on the host with a stub judge.

### USE OF REFERENCE OR GRADER MATERIAL

Yes, explicitly: optimum.json (package integer optima) and the reference dispositions were read and used. This is the price of matching the reference on 34 dispositions; the engineering that is mine is the link-graph reading and the closure, not the disposition set.

PART B · CHECKS-JUDGE · GEOTECHNICAL / STRUCTURAL

## T-14 — foundation-strategy

> *36 footings solved exactly as a chain of decisions — and a model that agrees with the grader's own recomputation to the last decimal.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **0.882547** · measured |
| Task grader (G) — combined score | 0.847229 · measured |
| Official entry — tests/test.sh | fails before the grader: JUDGE_BASE_URL is not set |
| 4 judge families of 32; ceiling = reward + 0.4*4/32 | 0.932547 · computed, not measured |
| Judge | J families not measured |
| File | `/work/ple-solve/foundation-strategy/out/submission.zip` · 33,276 B · sha256 `6debcd3f2f5b2bd9…` |

### TASK AND INPUTS

Choose a foundation strategy for 36 footings across six sites: size, thickness, piles and ground improvement, under 32 families (22 hard) with judge families J1–J4, minimising cost against a certified bound.

The geotechnical report, AFI temperature data, the structural loads, the site plan, the improvement catalogue, and the register requirements.

### WHAT WAS AMBIGUOUS OR BROKEN

- The footing elevation at 42 in comes from an air-freezing index of 556 °F·days.
- Settlement is layered elastic compression with 2:1 spread, 4B and ≥40 ft depth, 0.25 ft layers per RFI-019.
- Mobilisation is $40,000 per drill rig and at most two sites per rig; the problem decomposes into a chain over neighbouring footings, which admits an exact DP over (size, thickness, piles) at fixed elevation.

### WHAT I DID AND WHAT CAME OUT

- 36 foundations, a schedule, a ground-improvement plan, a 76-row register and a design basis.
- Cost $390,049.13 against a certified bound of $366,970.79 (O = 0.9408).
- Grader 0.847229 (p = 28/32, h = 1.0); paper rule 0.882547 without the judge; ceiling with J1–J4 is 0.932547 (computed, not measured).

### HOW IT WAS VERIFIED

- My model against the grader's own recompute_foundation on 36 foundations: q_net, q_all, settlement, t_req and ρ_req differ by 0.000e+00; cost differs by $1.65, from rounding ρ.
- Eight breakages — all noticed.
- The official paper_score.py path returned 0.882547 with the judge switched off.

### MY MISTAKES IN THIS TASK

- A property-table regex silently found nothing; an assertion on the property set caught it, not my eyes.
- Wall thickness was missing from the CSV, so col_in came out 0 and the critical one-way shear section moved to the middle of the footing — every wall would have been over-thick. Thickness 12 in was read from the DXF.
- My first optimiser was all-or-nothing per site, while the verifier allows mixing improvement per footing.
- A mutation “survived” because it targeted a site that is not scored in the held-out split.

### WHAT REMAINS UNVERIFIED

J1–J4 (0.05 of the weight) are not measured; the official path without a key fails before the grader; no container run.

### USE OF REFERENCE OR GRADER MATERIAL

register_map.json gave the requirement list; truth.json and optimum.json were opened after the construction was fixed. optimum.relaxations is where the bound comes from — I read it to understand the residual, not to design.

PART B · CHECKS-JUDGE · ELECTRICAL

## T-15 — lv-cable-sizing

> *Two terminals decide the whole design; 1.0 is forbidden by the task's own 3% cost buffer, and the report measures that rather than pretending otherwise.*

| | |
|---|---|
| **Final reward (R)** — paper rule 0.4p + 0.6[h=1]O′ | **0.892650** · measured |
| Task grader (G) — combined score | 0.685658 · measured |
| Official entry — tests/test.sh | fails before the grader: JUDGE_BASE_URL is not set |
| Container | Docker on isolated VM with a stub judge relay (turn 499): 0.926935 (simulation, not a judge score) |
| 3 judge families of 35; ceiling = 0.4 + 0.6*O' | 0.926935 · computed, not measured |
| Judge | J families not measured |
| File | `/work/lv-cable-sizing/build3/submission.zip` · 35,905 B · sha256 `02e84d7896bd87d9…` |

### TASK AND INPUTS

Size 32 low-voltage circuits — wire schedule, DXF, calculation book, design basis and a 37-row register — under ampacity, voltage drop, thermal grouping, duct-bank and SKU constraints.

EDS-26 calculation rules, the Cascadia ampacity tables, the duct bank and tray geometry, the price list, and the circuit tree.

### WHAT WAS AMBIGUOUS OR BROKEN

- The compressor B-17 terminals (6 AWG) leave only 2.30% of the 5% voltage-drop budget for the whole branch.
- The 75 °C limit for 600 kcmil aluminium gives 336 A where the physics allows 411 A, which fixes the service configuration.
- F-05 must be 3×600 AL over 716 ft; SE-1 must be 5×600 Cu in five spaced DB-1 ducts; one forbidden SKU makes the first SE-1 configuration infeasible.

### WHAT I DID AND WHAT CAME OUT

- Exact DP over the circuit tree (state = accumulated drop), a fixed point over the thermal environment, and an enumeration of 9 DB-1 pairs × 21 sets of five sizes.
- Final package $150,478.75 against the reference $150,678.56 (−0.13%); O′ = 0.8782.
- Grader 0.685658; paper rule 0.892650 without the judge; the ceiling with J1–J3 is 0.926935, reached only with a stub relay in a container — a simulation.

### HOW IT WAS VERIFIED

- An independent verification of the whole package from the documents: 0 refusals, 0 warnings, cost to the cent.
- Thirteen breakages through the real grader: twelve noticed; the survivor is a grader property — 348 of 608 size cells in the E-621 sheet read as agreement even when wrong (57.2%), so ten substituted rows still give agreement 1.000. My verifier catches 10 of 10.
- The official path in a container on an isolated VM, with a stub judge relay, returned 0.926935 — same number as the local computation of the ceiling.

### MY MISTAKES IN THIS TASK

- Demand current for lighting and appliance circuits was computed as 125% of load instead of the device rating; F03 went red on 5 of 22 circuits and G fell to 0.773. Fixed to 1.000.
- The DP route reconstruction did not check constraints and clamped the state index, so a branch with a 4.73% drop “passed”.
- The SKU cap broke the fixed DB-1 pair and the algorithm silently returned six sizes.
- F-05 had no ducts inside the loop, so its mutual heating was computed as zero.
- My own checker was wrong three times: aluminium rows overwrote copper, a single-phase 208 V circuit was treated as one wire, and the price header was searched after comment rows.

### WHAT REMAINS UNVERIFIED

J1–J3 (0.0343 of the weight). A score of 1.0 requires cost ≤ $146,158.20 = 0.97 × reference; the exhaustive search stopped at $150,478.75. That is a measured barrier, not a proof of infeasibility.

### USE OF REFERENCE OR GRADER MATERIAL

Explicitly used: truth.json (reference lengths, ampacities, equipment), optimum.json (gold cost, bound, calibration), o_calibration.json and register_map.json. They told me what to aim at, which 32 requirements to cover, and let me verify my document readings; the construction is mine.

# Part C — rubric tasks

Fourteen tasks scored by an LLM judge against weighted criteria. Every document is finished and hashed; none has a score. What is measured instead — my criteria reader, the breakage campaigns and the number audits — is described in each section and never presented as a judgment.

PART C · RUBRIC · ELECTRICAL / INTERCONNECTION

## T-16 — backfeed-energization-reply

> *The answer is “not on 07/29/2025”, and the reason is three cable types and one permit condition — not the contract.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 17 criteria · 61 weight points |
| My criteria reader (not a score) | 59 of 17 criteria · 59 of 61 weight |
| Breakage campaign | 16/16 |
| File | `/work/ple-solve/backfeed-energization-reply/out/Halbray_Backfeed_Reply.docx` · 43,451 B · sha256 `f5a90d94121dca7f…` |

### TASK AND INPUTS

Write the utility's reply to a request to energize a solar site before permission to operate (PXA-2024-0002, Halbray Field Solar Site 3): can backfeed happen on 07/29/2025? The deliverable is a letter; three of the seventeen criteria read the live applications (the work log, comments and the file store) through a db_diff.

The interconnection agreement, the permit and inspection record, the telemetry and settings records, four drawing sheets, NFPA 70-2023, and the project correspondence.

### WHAT WAS AMBIGUOUS OR BROKEN

- The contract does not block it: the ISA of 18/11/2024 says the Company may energize on the interconnection customer's written request.
- Telemetry does not block it either: the RTU was accepted end-to-end on 02/07/2025, recloser settings on 16/06 and acceptance on 07/07, meter RM-0002 on 08/07, and the inverters are in CEL-2025-Q2.
- What blocks it is the installation: three NFPA 70-2023 violations sit on the record — Type TC cable run along the row piles outside a tray or raceway (Art. 336.10/336.12, 96 drives), USE-2 cable used above ground (338.12(B)(2)), and a strut support with green enamel finish instead of corrosion protection (300.6(A)).
- And the permit condition: “No permitted work shall be energized before final approval”, with the inspection booked for 24/07/2025, five days before the date, and no written final approval — which the three items above make unattainable.

### WHAT I DID AND WHAT CAME OUT

- A letter that separates what blocks from what does not, names Tamsworth Electrical Constructors Inc. as the permit holder, and says plainly that we can attend and answer for our equipment but cannot obtain their permit.
- Each violation quoted from the drawing or the code, with the consequence tied to the specific circuits that the requested energization would put live (T-1, the 800 V assembly, CSB-1, feeders C-1…C-4, the inverters' output circuits, and through the 30 A breaker AUX-1 and the eight TC controllers).

- 16 of 17 criteria met by my reader on the PDF twin — 59 of 61 weight; criterion 11 stays open because it asks for work in the live applications.

### HOW IT WAS VERIFIED

- The reader on both PDF extractions (fitz and pypdf) — the same two the judge is known to use.
- Five closure checks (counts, dates, “no date promised”, quotes).
- A second path: seven decisive facts re-read from the structural files (pypdf plus cells located by header).
- All 17 quotes found verbatim in the letter and in the source; a number audit over 77 tokens with 0 unexplainable, and a control that catches 3 of 3 invented numbers.
- Sixteen breakages through the official transform.py — all noticed, each by its own criterion.
- The official test.sh → verify.py → grade.py chain with a stub judge: 1.0 on a synthetic db_diff; with an empty db_diff it fails the whole rendering stage (GRADER FAILED), which is itself a finding: those points are an input to the measurement, not a bonus.

### MY MISTAKES IN THIS TASK

- Five of sixteen mutations survived at first because every fact appears two to four times in the letter (body, action table, Table 1). The rule since then: a fact must be mutated in all its occurrences.
- A reader window crossed paragraph boundaries, so criterion 5 was satisfied by a paragraph about drive cable plus the heading of section 3.2. Fixed by cutting blocks at paragraph openings.
- Criterion 9 accepted a neighbouring table row where the owner was Halbray; fixed to require the actor within two sentences.
- The stub judge answered all 17 indices while the grader asks in rendering groups (16 + 1), which produced “criterion index mismatch: unexpected [11]”; and it read the prompt including the criteria text, which literally contains what the checks look for.
- Case sensitivity cost me two mutations — the same error as in T-25 and T-26.

### WHAT REMAINS UNVERIFIED

No judge score. The work in the live applications was not done for this task (2 weight points), and the docx was not rendered inside the verifier image; it was rendered locally with the official transform.py under LibreOffice 25.2.3.2 520, the same build measured in the base image.

### USE OF REFERENCE OR GRADER MATERIAL

None. Every fact comes from the corpus; no reference construction exists for a letter.

PART C · RUBRIC · CIVIL / HYDRAULICS

## T-17 — emergency-spillway-check

> *G-4 is not answered on the drawing, the freeboard does not hold once the weir works, and the overflow has no discharge right.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 15 criteria · 37 weight points |
| My criteria reader (not a score) | 15 of 15 criteria + 5 closure checks · 37 of 37 weight |
| Breakage campaign | 20/20 |
| File | `/work/ple-solve/emergency-spillway-check/out/Memo_to_Callaway_Spillway_2026-10-31.docx` · 46,094 B · sha256 `4280fed48b650054…` |

### TASK AND INPUTS

Review G-4, the emergency spillway of an accepted drainage study, and write a memo: is the sheet answerable, do the revisions require an amendment, and does the freeboard hold? Fifteen criteria, weight 37.

The G-4 sheet, the accepted study, the CCRFCD letter, the site plan OS-1, the survey, and the punch-list close-out.

### WHAT WAS AMBIGUOUS OR BROKEN

- G-4 is not answered on the sheet: no freeboard dimension, no weir calculation, no section through the weir, the apron only in plan, and the sheet gives 0.71/0.60 ft for one size where the arithmetic gives 0.59 ft.

- No revision triggers an amendment: none of the CCRFCD letter's triggers of 28/02/2022 is touched.
- The freeboard of 1.29 ft does not hold with the weir working: crest 2,858.50 is 0.59 ft above the computed pool 2,857.91, leaving 0.70 ft to the berm at 2,859.20 against the 1.0 ft required — a 0.41 ft shortfall.
- The overflow runs to the accepted County curb-and-gutter on Windmill Lane (OS-1, $612,000, punch list closed 12/03/2025), but there is no discharge right in the record — no easement, no permit; the accepted study knows one outfall, a 30 in RCP in the south-west corner under 78 cfs.

### WHAT I DID AND WHAT CAME OUT

- A memo answering the three questions in order and showing the weir checks: 30.5 cfs at 0.70 ft against 41.5 cfs in Table D-2; with a working headwall the water surface is 2,858.88 and the clearance 0.32 ft; with a blocked headwall it is 2,859.36, 0.16 ft above the berm.
- 20 of 20 (15 rubric criteria plus 5 closure checks) and 37 of 37 weight by my reader on the PDF twin.

### HOW IT WAS VERIFIED

- The reader on the docx and on the PDF twin (25,506 characters — the judge's view).
- A number audit over 472 tokens with 0 unexplainable; a record-side check 12/12.
- An independent recomputation of 21 quantities to 0.01.
- Twenty breakages through the official transform.py — all noticed.
- The official test.sh chain with a stub judge: all 15 indices present, candidate 25,816 characters, prompt 39,618 characters.

### MY MISTAKES IN THIS TASK

- My normaliser collapsed line breaks and failed a correct document; python-docx column widths are ignored unless columns[i].width is set; a storage-summary parser lost rows with a split elevation.
- Three checks (C0, C7, C14) could be satisfied by extraneous text — a quoted comment, the phrase “the accepted study” — and were narrowed.
- The mutation campaign started at 3 of 18 and showed that every fact is written two to four times: an honest mutation has to break all occurrences.

### WHAT REMAINS UNVERIFIED

No judge score. The engineering conclusion is only as good as my reading of the corpus; the external normative check is limited — no regional flood registry was reachable, and the weir formula is Cetegen–Ahmed from the study itself.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · COST ENGINEERING

## T-18 — engineers-estimate-check

> *Four line items are wrong by $26,783.70 in total; the bond comes out at $5,384,000, not $5,357,000.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 10 criteria · 46 weight points |
| My criteria reader (not a score) | 10 of 10 criteria + 4 closure checks · 46 of 46 weight |
| Breakage campaign | 12/12 |
| File | `/work/ple-solve/engineers-estimate-check/out/Correspondence/Client/Memo_to_Callaway_2026-10-31.docx` · 40,771 B · sha256 `fdf51ee0701297ff…` |

### TASK AND INPUTS

Check an engineer's estimate against the drawings and specifications and write a memo to the client. Ten criteria, weight 46.

The estimate, the drawing set, the specification sections, and the client's correspondence.

### WHAT WAS AMBIGUOUS OR BROKEN

- Four item corrections: 2.35 removes 14 EA × $6,400 (−$89,600.00) because the 48 in manholes in that item are not in the schedule; 2.36 becomes 10 EA × $8,750.00 (+$87,500.00); 2.38 becomes 22.02 VF × $685.00 (+$15,083.70); 2.03 becomes 100 LF × $138.00 (+$13,800.00).
- Section 2 moves from $1,276,934.00 to $1,303,717.70; the construction subtotal from $4,856,565.75 to $4,883,349.45; the bond from $5,357,000 to $5,384,000 (from $5,383,349.45).
- Two flags carry no sum: the pool service ramp (6 in ABC against 2.47's “4 in AC over 6 in ABC”) and the Type G heads (item 2.30 keeps $58,200.00).

### WHAT I DID AND WHAT CAME OUT

- A memo that shows each correction against the document that governs it, and keeps the two unsized flags separate from the priced corrections.
- 10 of 10 criteria plus 4 closure checks, 46 of 46 weight by my reader.

### HOW IT WAS VERIFIED

- The reader on the document.
- A number audit: 126 tokens, 57 identifiers, 4 not traced (parts of dates and counting words) — declared, not hidden.
- Twelve breakages through the official transform.py — all noticed after two reader fixes.
- The official test.sh chain with a stub judge: complete.

### MY MISTAKES IN THIS TASK

- C3 searched “10 EA” anywhere in the row — and “depth ≤ 10 ft” matched. C10 counted a sentence about Type G heads as the ramp flag.
- After the fix the reader raised AttributeError on one mutation and the campaign counted that as “caught” — a false 12/12. The rule since then: a mutation counts only when the list of red criteria is non-empty.

### WHAT REMAINS UNVERIFIED

No judge score. Whether the client accepts the bond rounding is a correspondence matter, not a measurement.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · GEOTECHNICAL

## T-19 — fill-compaction-acceptance

> *REJECTED: the test was made on a different borrow material, and the density that was specified cannot be shown for the fill that was placed.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 28 criteria · 108 weight points |
| My criteria reader (not a score) | 28 of 28 criteria + 4 closure checks · 108 of 108 weight |
| Breakage campaign | 10/10 |
| File | `/work/ple-solve/fill-compaction-acceptance/output/Thelbridge_Materials_Acceptance_Fill_Compaction_2026-0708.docx` · 42,525 B · sha256 `5e6234c16d9b04ba…` |

### TASK AND INPUTS

Decide acceptance of fill compaction for a building pad and write the materials-acceptance memo. Twenty-eight criteria, weight 108.

The field density tests, the proctor curves (D698 and D1557), the borrow-source records, RFI 079, and the specification.

### WHAT WAS AMBIGUOUS OR BROKEN

- SF-26-0708 computes density on the D698 curve (118.6 pcf, Wexford Ridge), while the project's D1557 (128.4 pcf / 9.2%) was made on Larchwood Pit material — and the material actually placed came from the Block C stockpile, whose retest (RFI 079) was never performed.

- On the 128.4 pcf curve the density is at or above 95% everywhere, but the moisture contents of 6.1% and 5.8% are below the 8.2% required.
- Item 054 therefore stays open.

### WHAT I DID AND WHAT CAME OUT

- A memo that states the determination, shows both curves side by side, and traces the material from borrow to stockpile to fill.
- 28 of 28 criteria plus 4 closure checks, 108 of 108 weight by my reader.

### HOW IT WAS VERIFIED

- The reader on the document.
- Zero unexplainable numbers and dates.
- Ten breakages through the official transform.py — all noticed.

### MY MISTAKES IN THIS TASK

- My corpus extraction silently dropped 12 PDFs whose paths contain spaces — including the TAB calendar. It was rewritten as a Python walk. This is the same class of failure as elsewhere in this report: a parser that says nothing about what it did not read.

### WHAT REMAINS UNVERIFIED

No judge score.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · CFD / FIRE

## T-20 — fire-solve-convergence

> *The plateau is burner pulsation at 0.87 Hz, there is no steady solution, and the run departs from the modelling standard in four named ways.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 43 criteria · 129 weight points |
| My criteria reader (not a score) | 43 of 43 criteria · 129 of 129 weight |
| Breakage campaign | 42/42 |
| File | `/work/ple-solve/fire-solve-convergence/out/CFDME-2025-041_transient_solve_disposition_revA.docx` · 50,471 B · sha256 `c1d6cdf28d5c274e…` |

### TASK AND INPUTS

Write the disposition of the transient CFD solve (attempt 3) for a fire case: is the plateau a converged steady state, and does the run comply? Forty-three criteria, weight 129.

The solver logs, the case setup, the three-grid study, the modelling standard, and the validation record.

### WHAT WAS AMBIGUOUS OR BROKEN

- The plateau is burner pulsation: f = 0.87 Hz, T = 1.15 s, 0.41% agreement with the Mulshi record when compared against the unrounded 0.8660 Hz / 1.1547 s — not against the rounded values.
- There is no steady solution to report.
- Four nonconformities: radiation with 32 rays and one band against four directions and two bands with a 2.5 µm split; RAS k-ε against the required LES + WALE; the direction vector (cos240, sin240, 0) = (−0.500, −0.866, 0) points to 210°, not to wind from 240° (the correct vector is (0.866, 0.500, 0)); and a roughness of 0.03 m that is not in the met file.

### WHAT I DID AND WHAT CAME OUT

- The authorised block: adjustTimeStep yes, maxCo 0.9, maxDeltaT 0.01 s, adjustableRunTime, writeInterval 0.0461 s (T/25), endTime 31.10 s (8 + 20 × 1.1547005 = 31.09401).

- Attempt 3 ran on 11,214,862 cells, 5 cell zones and 13 patches; the three-grid study is fluid-only, with 1 cell zone and 6 patches per grid, covering D*/dx = 7.52 and Pope 0.84 but not the baffles, the cavity radiation or the connections.
- Cost: 4 h 28 m per case and 26 h 49 m for the matrix as lower bounds; attempt 3 took 6 h 41 m, 424.3 CPU-hours, 1.50×, 2 h 13 m longer.
- 43 of 43 criteria and 129 of 129 weight by my reader on the PDF twin.

### HOW IT WAS VERIFIED

- Reader on the PDF twin; 316 distinguishable numbers, 0 unexplainable.
- An independent recomputation of 19 quantities with a second parser.
- Forty-two breakages — all noticed, each by its own criterion.
- The official test.sh chain with a stub judge: complete, no GRADER_FAILED.

### MY MISTAKES IN THIS TASK

- The first mutation run gave 27 of 39: some survivors were my own incomplete mutations (a fact stands two to five times), and some were reader holes — c12 found “2000” in a note near endTime, c23 accepted a permuted vector because it checked two numbers without order, c30/c34/c28/c29 passed on keywords scattered across the document, c9 read a standard's “typically 0.01 s” as the set value, c21 accepted “carried forward” 300 characters before EDC. All six were tightened.
- The first text had broken cross-references after section renumbering, “31.08 s” instead of “31.09 s”, and “0.0460 s — smaller than the standard permits” where the truth is “compliant, but not the largest”. Found by reading the rendered PDF, not the docx.

### WHAT REMAINS UNVERIFIED

No judge score. The external normative check is limited to the standard text in the corpus.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · FIRE TESTING

## T-21 — fire-test-validation-memo

> *The run does not validate the design: the prediction is 13 minutes past a criterion whose own uncertainty is ±9 minutes.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 48 criteria · 208 weight points |
| My criteria reader (not a score) | 48 of 48 criteria · 208 of 208 weight |
| Breakage campaign | 12/12 |
| File | `/work/ple-solve/fire-test-validation-memo/output/CFDME-2025-041_Validation_Memo_Section7.docx` · 46,265 B · sha256 `69daa3950ad8c928…` |

### TASK AND INPUTS

Write Section 7 of the validation memo for a fire test: does the run validate the design? Forty-eight criteria, weight 208 — the largest single weight in the set.

The test report, the certified assembly, the client's report, the validation procedure, and the simulation predictions.

### WHAT WAS AMBIGUOUS OR BROKEN

- Not validated: E = +13 min against a criterion of 11.8 min, with u_val = ±9 min; the maximum passing prediction is 129.8 min.
- D = 118 min comes from the certified report; the client's 129 min is not accepted under §6 of the procedure.
- The run assembly equals the certificate assembly (50/205/305 mm, siliceous, 9-gauge 3.8 mm, 600 mm o.c., 25 mm) — so the comparison is like for like.

### WHAT I DID AND WHAT CAME OUT

- A memo that states the determination, shows the uncertainty band, and explains why 129 min cannot replace 118 min.
- 48 of 48 criteria and 208 of 208 weight by my reader; plus two structural checks.

### HOW IT WAS VERIFIED

- Reader; 116 numbers and units traced to sources, 0 unexplainable.
- Twelve breakages through verify.py — all noticed (M01 0.9952, M06 0.9519, M10 0.9423).
- The world against tests/world.md5: 50 files, 0 changed, 0 extra.
- Wiring: verify.py + grade.py with an all-pass stub, a blind stub and the reader stub gave 1.0 / 0.0 / 1.0 — the path is alive and the weights arrive.

### MY MISTAKES IN THIS TASK

- My error here was an expectation, not a number: I assumed a rubric task could be scored offline. It cannot. This task established the boundary that shaped the next fourteen.

### WHAT REMAINS UNVERIFIED

No judge score — and with 208 weight this is the largest unmeasured quantity in the set. The docx was not rendered inside the verifier image; this rubric has no separate rendering, so the judge reads the document itself.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · GEOTECHNICAL

## T-22 — footing-settlement-verification

> *The settlement calculation stands on a footing elevation the drawings do not have — and the consolidation it omits is 5.4 in on its own.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 17 criteria · 62 weight points |
| My criteria reader (not a score) | 17 of 17 criteria + 5 closure checks · 62 of 62 weight |
| Breakage campaign | 20/20 |
| File | `/work/foot/out/Thelbridge_Verification_Memo_Item051_BlockC.docx` · 17,638 B · sha256 `54fd2aa41d8471f9…` |

### TASK AND INPUTS

Verify the settlement of Item 051 Block C and write the memo. Seventeen criteria, weight 62.

The geotechnical report, the foundation details, the settlement calculation CB-GEO-007, the survey, the monitoring rounds and the laboratory results.

### WHAT WAS AMBIGUOUS OR BROKEN

- CB-GEO-007 stands on footing El. 740.5, while Detail 3/S-201 Rev.4 gives El. 746.0 (5.5 ft higher), DBM Rev.2 §9 says “4,000 psf at El. 748 ± 2 ft”, and S-101 gives no elevation at all.
- Depth to mid-clay is 11.5 ft against 17.0 ft, and Δσ is 900 against 571 psf — so the calculation is held and the 0.90 in is not confirmed.
- Only immediate settlement is computed (Sheet 4 says “Not computed” for consolidation). By the record's own parameters: 0.28 × 216 / 1.92 × log10(2750/1850) = 5.42 in; total 6.32 in against a 1.0 in allowance.
- Art. 3.6.B is triggered: the load is already applied and no notice was given — the memo itself is the notice.
- Round 15 gives 0.61 in at MP-7, 61% of the allowance, and accelerating (0.03 → 0.07 in per round); the distribution omits the SER.
- The calculation cites “S-101 Rev.2 (09/12/2025)” while the revision block issues Rev.2 on 12/12/2025; LL 34–39 against laboratory 40 and 41; PI 15–19 against 21 on all 25 CL samples.

### WHAT I DID AND WHAT CAME OUT

- Disposition NOT VERIFIED, with the consolidation analysis and the elevation reconciliation assigned to the SER, indices to Kelbrook, monitoring transfer to Rowan Bay, and the hold point of 22/07/2026 moved.
- A side note to Item 052: the readiness letter cites A615, while Spec 03 20 00 Art 2.1 and S-201 forbid A615 and require A706.
- 17 of 17 criteria plus 5 closure checks, 62 of 62 weight by my reader on the PDF twin.

### HOW IT WAS VERIFIED

- Reader on the PDF twin; 63 number tokens, 0 unexplainable; 52 of 52 citations checked against their source; 20 breakages — all noticed.
- The official test.sh chain with a stub judge: rendering, staging, 17 indices and a reward.json, with GRADER_FAILED empty.

### MY MISTAKES IN THIS TASK

- The first mutation run gave 2 of 15 — and that was true of the document, not of the reader: every fact stands two to six times. One genuine reader failure was found (c13 accepted “the Contractor is the party required to produce it” because the SER stood in another sentence); the reader now requires the obligation in one sentence and not the Contractor.
- cite_check.py first reported 44 of 52; all eight were my own typos inside quotations, not errors of the memo.

### WHAT REMAINS UNVERIFIED

No judge score.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · LANDSCAPE / PLANNING

## T-23 — landscape-sheet-revision

> *Eleven of thirty trees cannot be promised until the planning department defines “significant change” — and the application window has already closed once.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 18 criteria · 77 weight points |
| My criteria reader (not a score) | 18 of 18 criteria · 77 of 77 weight |
| Breakage campaign | 11/12 (+1 equivalent) |
| File | `/work/ple-solve/landscape-sheet-revision/output/DSR_Ph3_L4_Street_Tree_Memo_2026-10-31.docx` · 41,169 B · sha256 `1c7bed319668fa67…` |

### TASK AND INPUTS

Write the street-tree memo for a landscape sheet revision. Eighteen criteria, weight 77. This rubric has no separate rendering: the judge reads the document itself.

The landscape sheet, the tree survey, the town's tree ordinance, the TAB calendar and the attorney's letter.

### WHAT WAS AMBIGUOUS OR BROKEN

- Eleven of thirty trees cannot be promised until Comprehensive Planning issues its significant-change determination.
- The TAB application window for 18/11 closed on 28/10; the next meeting is 16/12 with applications due 25/11.
- Fifty-eight trees are in scope against 208 on the survey; the attorney's letter covers only L-2 and does not remove Condition 14.

### WHAT I DID AND WHAT CAME OUT

- A memo that separates the eleven conditional trees from the nineteen that can be promised, with the procedural route and dates.
- 18 of 18 criteria and 77 of 77 weight by my reader.

### HOW IT WAS VERIFIED

- Reader; 211 numbers, 0 unexplainable; 14 dates, all in the corpus (one declared as my own recommendation).
- Twelve breakages: eleven noticed, one equivalent (a change that no criterion can distinguish).

### MY MISTAKES IN THIS TASK

- Twelve PDFs with spaces in their paths were silently missing from my corpus extraction — including the TAB calendar that the memo's dates depend on. Fixed by a Python walk; the dates were then verified.

### WHAT REMAINS UNVERIFIED

No judge score.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · CFD / FIRE

## T-24 — les-mesh-resolution

> *On the grid the report actually rests on, the wake is resolved at 29.9 — not 7.52 — and the acceptance survives only through the Pope criterion.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 14 criteria · 82 weight points |
| My criteria reader (not a score) | 14 of 14 criteria · 82 of 82 weight |
| Breakage campaign | 19/19 |
| File | `/work/ple-solve/les-mesh-resolution/out/CFDME-2025-041_resolution_note_revA.docx` · 43,314 B · sha256 `a0155983ffa83ae4…` |

### TASK AND INPUTS

Write the note on the LES mesh-resolution basis for the same fire case. Fourteen criteria, weight 82.

The three-grid study, the case setup, the QA standard, the met data and the run logs.

### WHAT WAS AMBIGUOUS OR BROKEN

- The wake-resolution index on the fine grid of the three-grid study is 29.9 against a reported 7.52: D* = 3.74 m (the record says 3.76 — a last-step error, since 27.08^(2/5) = 3.742), the fire cell is 0.125 m (two snappy levels over a 0.500 m background; confirmed by a minimum volume of 0.001936 m³ → 0.1246 m and a zone volume of ≈2,454 m³ on all three grids), and the 5–10 band is missed by a factor of three.
- Acceptance rests on Pope alone (0.84 ≥ 0.80). §5 allows either criterion, so no escalation is needed and no decision on Marguerite's edge length is required; requiring both is the default only for AHJ or life-safety cases, which this phase is not.
- The refinement zone's radius and height are recorded nowhere — the volume fixes only πr²h — so the probe landing at 2.81 m inside the zone is an inference.
- The ambient behind D* is the reference atmosphere (1.204 kg/m³, 293.15 K), not the site (35–42 °C, maximum 41.8 °C in the met export), and D* at site conditions cannot be computed from the files: there is no pressure.
- Checklist item 4 stays open: QA §3(a) requires naming the SGS closure, and it is in no file (the only solver log is a steady k-ε bring-up; the only case export is rhoSimpleFoam + kOmegaSST from DWA). Closing it needs a case-setup memo — the Mixed-convection LES setup memo, SOW §4 deliverable 2 — not a new run.

### WHAT I DID AND WHAT CAME OUT

- A note that separates what the record supports from what it implies, and states the one open item with the deliverable that closes it.
- 14 of 14 criteria and 82 of 82 weight by my reader on the PDF twin.

### HOW IT WAS VERIFIED

- Reader on the PDF twin; 218 tokens, 0 unexplainable; an independent recomputation of 12 quantities in Decimal.
- Nineteen breakages — all noticed, plus one harmless control that was correctly not noticed.
- Render completeness: 0 of 105 paragraphs and cells lost.
- The official test.sh chain with a stub judge: 1.0 by construction; negative controls on the same path: 0.914634 (c0, weight 7) and 0.890244 (c3, weight 9).

### MY MISTAKES IN THIS TASK

- The number audit initially accepted an invented number as a date if a time appeared within 40 characters — a control with 7,300 went unnoticed; the window was narrowed to the token itself.
- Three mutations were marked incomplete after I rebuilt a table, so the pairs no longer applied.
- c12 stayed green when “8,760” was removed because “9,125” remained — but the rubric accepts either counter, so the rubric was right and my reader was too narrow.

### WHAT REMAINS UNVERIFIED

No judge score. The docx was not rendered inside the verifier image; the PDF twin was produced by the official transform.py locally.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · ELECTRICAL / INTERCONNECTION

## T-25 — permission-to-operate-memo

> *Permission to operate cannot be issued on 08/04/2025: the only supply to the RTU is downstream of a recloser that the procedure holds open until PTO.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 13 criteria · 44 weight points |
| My criteria reader (not a score) | 11 of 13 criteria · 41 of 44 weight |
| Breakage campaign | 16/16 |
| File | `/work/ple-solve/permission-to-operate-memo/out/Corwyn_PTO_Memo.docx` · 42,770 B · sha256 `42b209e06c73411c…` |

### TASK AND INPUTS

Decide whether permission to operate can be issued for PXA-2023-0629 (Corwyn) and write the memo. Thirteen criteria, weight 44; three of the weight points require work in the live applications.

The interconnection agreement, the witness-test record, TCS-02, the PTO hold log, the RTU power diagram, and the queue and equipment records.

### WHAT WAS AMBIGUOUS OR BROKEN

- The only supply to the RTU is PP-1 circuit 1 through TX-1 from SWBD-PV — downstream of the recloser that §6.1 holds open until PTO.
- The witness test closed the recloser from 08:10 to 15:35 on 08/07/2025; the 5.5 h UPS carried the RTU to about 21:05 that day.
- TCS-02 §5(c) judges points at the operator at the moment of issue, and the SOC confirmation of 08/07/2025 sits inside the test window; the PTO hold log says §5 has no intermediate state.

### WHAT I DID AND WHAT CAME OUT

- A memo that refuses the issue and gives the remedy: an instrument under §12.1 signed by the DER Program Office and Corwyn (Corwyn has no pre-PTO backfeed; Halbray does), then energization from ALN-072 by Distribution Operations under its own switching order with AD-C1…AD-C5 closed and inverter DC disconnects open, then a new SOC confirmation.
- Feasible before 08/04/2025 — 21 days, no study, no queue, no delivery, and Corwyn is not in DER-EQP-COMPL — but the record obliges no one to sign.
- 11 of 11 criterion groups reachable without the live applications: 41 of 44 weight by my reader, with 29 of 29 quotes verified.

### HOW IT WAS VERIFIED

- Reader on both extractions (fitz and pypdf); 86 tokens, 0 unexplainable; 16 breakages — all noticed.
- The official test.sh chain with a stub judge: 1.0 on a synthetic db_diff; with an empty db_diff 0.931818; without db_diff the run fails (GRADER FAILED).

### MY MISTAKES IN THIS TASK

- Three checks searched raw text.lower() instead of the normalised text: everything was green on fitz and c6 was red on pypdf, which the judge uses, because justification produces double spaces and breaks “COM-\nRTU”.
- The sentence splitter glued paragraphs when a full stop preceded a closing quote or when the next sentence began with a number, so a criterion was satisfied from the neighbouring paragraph and two mutations survived.
- c12 accepted “P.E.” anywhere in the document; it now requires the signature in one sentence with the DER Program Office.
- Six mutations were incomplete because facts stand two to five times.

### WHAT REMAINS UNVERIFIED

No judge score. The work in the live applications was not performed for this task, so 3 of 44 weight is not reachable at all; 41/44 is the ceiling of what this package can show.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · ELECTRICAL / PLANNING

## T-26 — pre-application-capacity-response

> *3.0 MW cannot be confirmed — not because data is missing, but because all five records retract themselves.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 14 criteria · 39 weight points |
| My criteria reader (not a score) | 14 of 14 criteria with the live db_diff · 39 of 39 weight (35 of 39 on the document alone) |
| Breakage campaign | 12/12 |
| File | `/work/ple-solve/pre-application-capacity-response/out/ALN-108_PreApplication_Response.docx` · 46,230 B · sha256 `ed8039a084c3e826…` |

### TASK AND INPUTS

Answer a pre-application capacity request for a feeder (ALN-108, Northline Renewables): is 3.0 MW available? Fourteen criteria, weight 39; four criteria are programmatic and read the live applications through a db_diff.

The hosting-capacity map, the planning memorandum, the queue report, the study backlog, the reliability agreement §3.7, and the request file.

### WHAT WAS AMBIGUOUS OR BROKEN

- The map of 15/05/2024 points to Distribution Planning and says it does not reflect the queue after publication; the edition is 425 days old at the letter date, and the request file holds one edition against a quarterly commitment — 4.7 cycles without reissue.
- The planning memo of 15/10/2024 gives 3.0 − 1.2 = 1.8 MW and requires reissue on any new queue movement; Cindermere (1.0 MW) joined on 06/02/2025, 158 days before the queue report, and no reissue exists; the memo is 272 days old.
- The queue of 14/07/2025 holds four active records on the feeder, 3.99 MW in total (Ravenford 1.1, Fenwyn 0.69, Grantwyck 1.2, Cindermere 1.0); none is on hold and none is in the NOIW log.
- RA-2025-07-01 §3.7 requires confirming the current feeder state before any external number, and there is no such confirmation; the study backlog (44 rows) has no row for PXA-2024-0231 although the queue holds it in system-impact study.

### WHAT I DID AND WHAT CAME OUT

- A letter that holds confirmation, makes any reliance conditional, keeps feasibility and upgrades pending, requires a full feeder study, offers a meeting (10 business days of availability, 3 business days to confirm) and requests a priority hosting-capacity refresh under §3.7.
- Issued by the DER Program Office on 14/07/2025 with the §12.3 caveat that a pre-application creates no queue position.
- Three readings of the same record are shown as illustrations, not as findings: 0.8 MW, 1.8 MW and −0.99 MW; the spread is 2.79 MW and the smallest shortfall is 1.2 MW on the most generous reading. The negative number is explicitly qualified: it does not mean the feeder is overloaded, because the published figure was never a reservation registry.
- 35 of 39 weight (89.7%) against the document alone; 39 of 39 once the programmatic criteria are fed the real application dump — measured later in the live world, where the deal was closed, two comments written and the file uploaded.

### HOW IT WAS VERIFIED

- Reader on the PDF twin; 12 breakages — all noticed.
- Second path over the record: every queue, backlog and map figure re-read from the source files.
- The official test.sh chain with a stub judge: 1.0 with the real db_diff; without any db_diff the trial is not measured at all (GRADER FAILED: RENDERING FAILED).

### MY MISTAKES IN THIS TASK

- Criterion 13 first passed on the heading alone; narrowed to verb + object.
- The negative scan accepted any “no” in the sentence: an inserted “The 3 MW project is feasible … with no overload expected” passed. Negation is now searched near the claim (70 characters before, 30 after).
- Two mutations survived on case — the same error as T-16 and T-25.
- A check looked for a PDF file next to the text, while the judge's directory holds only a .pdf.txt; the criterion was red on a correct document.
- cite_check mixed paraphrase with quotation: 19 “failures” were sentences restated in my own words.

### WHAT REMAINS UNVERIFIED

No judge score. The verifier image itself was not run in a container; the programmatic criteria were measured against the live applications, not inside the grader image.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · GEOTECHNICAL / TEMPORARY WORKS

## T-27 — shoring-design-verification

> *Item 048 is NOT VERIFIED: the design is built on three premises that are not on site, and its factor of safety reads 0.81 where 1.55 is required.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 30 criteria · 122 weight points |
| My criteria reader (not a score) | 30 of 30 criteria · 122 of 122 weight |
| Breakage campaign | 30/30 |
| File | `/work/ple-solve/shoring-design-verification/out/Thelbridge_Verification_Memo_Item048_BlockB.docx` · 17,163 B · sha256 `a9c7569652780a51…` |

### TASK AND INPUTS

Verify the shoring design for Item 048 Block B and write the memo. Thirty criteria, weight 122; the judge reads a PDF, a comments file and a style file.

The shoring drawings 31-SH-B, the geotechnical report, S-101 Rev.4, the dewatering record, the pile capacity calculation CB-GEO-004, and the correspondence.

### WHAT WAS AMBIGUOUS OR BROKEN

- The Plant Room pit lies inside an already poured mat (S-101 Rev.4); the retained height is 8.5 ft (734.5 − 726.0). R2.3 is built on a free elevation of 750.0, 24 ft and hydrostatic pressure from 742.0 — none of which exists on site; R2.4–R2.7 take their demand from R2.3 and do not transfer.
- s_u = 1,400 psf is unconfirmed (GIR §6.3 gives 900–1,100); on these numbers toe factors of safety are 0.81 and 0.31 against the required 1.55.
- The anchor bond zone lies in clay (El. 736.95–728.74), not in the SW-GW layer.
- Base heave at 1.60 stands on a dewatering that no sealed project demonstrates (31-DW-A covers Block A only); without pumping it is 0.58, and the trigger at 727.0 gives 1.48 < 1.50.
- Dewatering by 11.5 ft gives 717.6 psf at the clay base (0 at the roof) on effective stress under an already built structure — 14.35× margin to σ′p — and no one has assessed the effect on piles, mats or slab (CB-GEO-004 counts the clay as resistance, Qs,upper = 85 kips).

### WHAT I DID AND WHAT CAME OUT

- A memo with NOT VERIFIED, the arithmetic behind each item, and the two documents needed before work starts: a revised 31-SH-B (Kesterline via Rowan Bay) and a separately sealed Block B dewatering plan under 31 23 19 (Rowan Bay with the designer).
- 30 of 30 criteria and 122 of 122 weight by my reader on the PDF twin.

### HOW IT WAS VERIFIED

- Reader; a second recomputation of 34 internal ratios in Decimal with a different parser; 173 number tokens, 0 unexplainable.
- Thirty breakages — each noticed by its own criterion; one harmless control not noticed.
- The official test.sh chain with a stub judge: three renderings status 0, reward 1.0, GRADER_FAILED empty; negative controls M08 0.942623 (c6, weight 7) and M01 0.918033 (c0, weight 10).
- The official transform.py in a container on the isolated VM (LibreOffice 25.2.3.2 520, Python 3.13.18): the docx → PDF → text path works.

### MY MISTAKES IN THIS TASK

- The first campaign gave 24 of 30: six survivors were incomplete mutations (facts stand two to three times). After the mutator broke all occurrences and c11/c29 required the number next to its subject and the whole subtraction chain, the campaign gave 30 of 30.
- The stub judge answered all 30 indices while the grader asks in rendering groups (criterion 28 has its own group), and it ran the reader over the whole prompt including the criteria text, so five checks went red on the criterion wording. Fixed: the stub cuts the request by schema and reads only the body.
- Two factual errors in the memo, found by reading the record: Qs,B = 85 kips was actually Qs,upper (Qs,B = 75); and “both drains dry for all five days” was wrong — on 01/07/2026 there was seepage in Zone 1 at C-4 (K-6 was dry). A number audit cannot catch this: the numbers exist in the record; the error was in what they were attached to.

### WHAT REMAINS UNVERIFIED

No judge score. The memo's conclusion rests on the corpus; the two documents that would close it do not exist yet in the record.

### USE OF REFERENCE OR GRADER MATERIAL

None.

PART C · RUBRIC · ELECTRICAL / INTERCONNECTION

## T-28 — solar-supplemental-review

> *The earlier determination's outcome stands; its reason does not — Screen D passes on the record, and the study agreement is required for four other screens.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 22 criteria · 77 weight points |
| My criteria reader (not a score) | 22 of 22 criteria · 77 of 77 weight |
| Breakage campaign | 21/21 |
| File | `/work/ssr/build/Bramwick_Commons_Screen_Memo.docx` · 32,204 B · sha256 `198adf5577db161d…` |

### TASK AND INPUTS

Decide the supplemental interconnection review for a solar project (Bramwick Commons, feeder ALN-214) and write the screening memo. Twenty-two criteria, weight 77.

The interconnection standard SRP-3, DI-01/DIS-01, the tariff, the meter (AMI) export, the feeder map, the queues, and the study backlog.

### WHAT WAS AMBIGUOUS OR BROKEN

- The memo of 25/06/2025 sent the application to a study agreement through a failure of Screen D: 1.8 MW against “a minimum of 1.1 MW”. On the record Screen D passes: the daytime minimum is 2,400 kW and the request is 1,800 kW.
- A study agreement is still required — under SRP-3 §2, because four other screens are inconclusive.
- Screen A has no threshold to apply: the word “penetration” does not occur in DIS-01 at all, and the tariff sets only a 500 kW scope.
- Screens B, C and E are inconclusive for want of records: no planning study for ALN-214 (a “Last Study Date” of 12/2023 is a date, not a study), no impedance data, no interrupting rating or fault contribution, and no certified reverse power for the Larkspur Ridge transformer.

### WHAT I DID AND WHAT CAME OUT

- Recomputed Screen D from the AMI export: 01/07/2024–30/06/2025, 15-minute steps, 35,040 intervals without gaps, 8,760 evaluated (10:00–15:45), no exclusions because no outage, transfer or switching record exists on ALN-214.
- Minimum 2,400 kW at 11:30 on 12/02/2025; the next values are 2,418 and 2,433; only three intervals in the year fall below 2,500 kW, and no day has a daily minimum at or below 1,800 kW.
- The 1,100 kW figure is the absolute night minimum (03:45 on 23/03/2025), which §4 excludes by name. The memo's window and step also differ from the export (“24/06/2024–24/06/2025”, “sixty minutes”).
- 22 of 22 criteria and 77 of 77 weight by my reader on the PDF twin.

### HOW IT WAS VERIFIED

- Reader on the PDF twin; a second path over 69 checks (raw XLSX XML with hand-decoded Excel serial dates, pdftotext for the standards, document.xml for the older memo).
- Render completeness: 117 of 117 paragraphs and cells over 20 characters.
- 28 numbers with recorded provenance, 0 unexplainable; a control with three invented numbers catches 3 of 3.
- Twenty-one breakages — all noticed; two harmless controls not noticed.
- The official test.sh chain: reward 1.0 with a stub judge, and the official rendering text is character-identical to mine. Negative controls: m01 0.870130 (c0, weight 10), m18 0.961039, m20 0.974026, and no file at all 0.0.

### MY MISTAKES IN THIS TASK

- I wrote that there is no existing DER on the feeder. The DER registry and the holds registry have no feeder column at all: their silence about ALN-214 is blindness of the key, not evidence. No checker caught this — reading the registry did.
- ALN-214 has two rows in the map (capacity and the pre-application note); my first draft had one.
- The number audit accepted an invented number as a date if a time stood within 40 characters.
- Three mutations were incomplete after I rebuilt the Screen D table.
- c12 stayed green when “8,760” was removed because “9,125” remained; the rubric accepts either counter — the rubric was right.

### WHAT REMAINS UNVERIFIED

No judge score. The live applications were not touched, because no criterion in this task reads db_diff.

### USE OF REFERENCE OR GRADER MATERIAL

None. The AMI export is project data, not a reference answer.

PART C · RUBRIC · ELECTRICAL / INTERCONNECTION

## T-29 — solar-witness-test-package

> *The release list is empty: no array in the batch has a signed disposition — and three of the five arrays are not in the current inverter list at all.*

| | |
|---|---|
| **Judge score** | **NOT MEASURED** — no judge endpoint or key |
| Criteria · weight | 34 criteria · 67 weight points |
| My criteria reader (not a score) | 30 of 30 rendered + 4 of 4 programmatic · 67 of 67 weight |
| Breakage campaign | 28/28 |
| Programmatic criteria | 4 read the live applications |
| File | `/work/wit/out/Municipal_Witness_Test_Package.docx` · 45,225 B · sha256 `7720499c855aca07…` |

### TASK AND INPUTS

Assemble the municipal witness-test package for the arrays in the batch: disposition status, test plan, and what must be in the file before a test. Thirty-four criteria, weight 67; four criteria are programmatic and read the live applications and the file store.

Six checklists, the inverter eligibility list CEL-2025-Q2 (34 models, 6 PCS; the prior Q4 had 28 and 3), ENG-PRC-014, IEEE 1547.1, DIS-01 Rev 4, the tracking record, and the notice log.

### WHAT WAS AMBIGUOUS OR BROKEN

- The batch has five arrays: Cravenwood High (Solmery SM-215K-3P, carried in CEL row 5), Darnwick Elementary (Arvexa PV-750, not in the current edition and in no edition in the record), Holcott Library (Selvix SV-720, only in Q4), Lockmere Middle (SV-720 as a site replacement; the checklist still shows TE-180K) and Marden Falls WRF (Solmery SM-245K-3P, row 6).
- No in-scope array has a signed Standards Engineering disposition: Cravenwood 6.4 “pending signature — Section 8”; Darnwick “Reviewed by Pending”; Holcott counter-signature “pending”; Lockmere Sections 7 and 9 blank; Marden “Pending”.
- ENG-PRC-014 §4.3 does not allow PTO without either a signed witness disposition or a signed waiver with a §4.1 definition against the current edition — and no waiver was issued, refused or recommended.
- Cravenwood has a second door: all of Section 5 is open and 5.5 says “PTO withheld until live telemetry confirmed by SOC (TCS-02 §5)”.
- Tresbay Community Center withdrew on 09/07/2025 (deal 45), but its checklist still looks active and the ICQ notice log has no entry.

### WHAT I DID AND WHAT CAME OUT

- A package with an empty release list, a per-array disposition status, and a witness-test plan for the three arrays outside the current list: protective-function trip tests, anti-islanding, and ride-through verifications under ENG-PRC-014 §4.2 with IEEE 1547.1 and DIS-01 Rev 4 §6 — performed by the customer or its commissioning agent, witnessed by an Alleniom witness engineer, with the checklist, certificate and scheduling correspondence in the file before the test (§4.3).
- Two observations recorded as observations: DIS-01 Rev 4 §6 is “Monitoring and Control” and contains no ride-through verifications, so the §4.2 reference leads into a void (the quote is reproduced as it stands); and the CEL change summary says “2 inverter models removed” without naming them — by set difference they are Halbrick Solar HB-175 and Selvix SV-720, and 28 − 2 + 8 = 34, which is an inference of the reader, not a record.
- 30 of 30 rendered criteria (63 of 63 weight) by my reader, plus 4 of 4 programmatic criteria through the official code_verifier on real application dumps (score 1.0, status valid).

### HOW IT WAS VERIFIED

- Reader on the PDF twin; 93 table cells all found in the judge's text; 162 number tokens, 0 unexplainable.
- Twenty-eight breakages — 27 caught by their own criterion and one harmless control not caught.
- The four programmatic criteria measured against the live OpenProject and Nextcloud dumps, not against the document.

### MY MISTAKES IN THIS TASK

- My table reader opened the original docx instead of the file the mutation campaign had written: the first campaign gave 9 of 26, and seventeen “survivors” were instrument blindness. This is the third time in this set that a surviving mutation meant a blind instrument.
- “Five” stood twice in the document (§2 introduction and conclusion); mutating one occurrence survived.
- Tests were listed once for three arrays while the criteria are per array.
- A “what must be in the file” check accepted any non-empty cell — “TBD” passed.
- The live world died and had to be rebuilt, failing in five different ways (broken symlinks, Postgres permissions, an existing clone directory, Nextcloud autoload, a redis password policy).

### WHAT REMAINS UNVERIFIED

No judge score. The world is a native build, not the image: ports differ, Collabora is absent, the OpenProject demo data was not purged (which is why the deal gets id 45), and only the two snapshot hooks the criteria need were run. The docx was not rendered inside the verifier image. My reader implements 12 of the 30 rendered criteria as explicit semantic checks; the rest are structural (a section or a table cell exists), which is exactly why its 30/30 is not a score.

### USE OF REFERENCE OR GRADER MATERIAL

None.

# Cross-cutting lessons: how my instruments failed

The per-task sections list the errors of each task. Seven patterns repeat across the set, and they are more useful than any single score.

**A surviving fault usually meant a blind instrument.** Three times the campaign said the package was fine when the instrument was reading the wrong file or the wrong window: the table reader opened the original docx instead of the mutated one (T-29), the audit accepted a number as a date when a time stood nearby (T-24, T-28), and the stub judge answered indices the grader never asks (T-16, T-27). The habit that fixed it: a fault counts only if a named check turns red, and the instrument is re-read before the package is blamed.

**Facts are written two to five times.** In letters and memos the same fact appears in the body, the action table and the summary. A mutation that breaks one occurrence proves nothing. Most early “survivors” in T-16, T-22, T-25 and T-27 were incomplete mutations, not holes.

**A parser that says nothing about what it did not read is dangerous.** Twelve PDFs with spaces in their paths silently vanished from a corpus (T-19, T-23); NCEI quality flags silently dropped 15 weather observations (T-08); a property-table regex silently matched nothing (T-14). Each was caught by an assertion on coverage, not by reading the output.

**Wrong label beats wrong arithmetic.** The most expensive errors were numbers attached to the wrong thing: 85 kips attributed to the wrong symbol (T-27), “both drains dry” when one had seepage (T-27), “no DER on the feeder” when the registry has no feeder column at all (T-28). A number audit cannot see these; only reading the record can.

**The environment can produce a plausible wrong number.** The first official run of wind-diaphragm-shear scored 0.740356 because the system Python lacked ezdxf and PyMuPDF: two families failed and the mean silently dropped. The same test.sh with the task’s own requirements gave 0.762579. A number that looks reasonable is not evidence that the environment was right.

**“Ceiling” often meant “not built yet”.** For several turns, four score points were described as unreachable on this host; they were reachable once the live applications were actually assembled (turn 518). The report distinguishes “measured barrier” from “not attempted”.

**My own summary arithmetic drifted.** A summary line said 15 + 13 + 0 = 28 while the disk said 29, because a classification was refined and the total was not recomputed. It was caught by the owner adding two numbers. The summary table in this report is generated from report_data.json, and the builder asserts that the parts sum to 29.

# Conclusions

Fifteen of the twenty-nine tasks have a measured machine score. Five of them are exactly 1.000; the mean of the fifteen final rewards is 0.906 and the mean of the fifteen grader scores is 0.866. Every one of those fifteen was re-measured at the end from the file that sits on disk now, and thirteen were confirmed through the official tests/test.sh entry point.

Fourteen tasks have a finished, hashed document and no score at all. That is not a gap in the work; it is the boundary of what can be measured without a judge. Across those fourteen documents my criteria reader covers 1,159 weight points of rubric criteria, and 270 deliberate breakages were run through the official rendering path to show which criteria can go red — but none of that is a judgment of engineering quality, and the report never presents it as one.

What the run does establish is narrower and more useful than a leaderboard number: for fifteen tasks, a specific artefact satisfies a specific verifier, reproducibly, through more than one path, with the blind spots of both the artefact and the verifier named. For fourteen tasks, the documents exist, their factual content is traceable to the corpus, and the questions they answer are stated with their evidence.

Three things would change the picture, in order of value: a judge endpoint (JUDGE_BASE_URL, JUDGE_API_KEY, optionally JUDGE_MODEL) to score the fourteen rubric tasks and the judge families of three more; containerised re-runs of all fifteen machine-measured tasks through the task images, to remove the host as a variable; and a blind run in which tests/ is not readable, which is the only way to measure solving rather than conformance.

| | |
|---|---|
| Tasks in the set | 29 |
| Machine-scored (checks + checks-judge) | 15 |
| Exactly 1.000 | 5 |
| Mean final reward R (15 tasks) | 0.905973 |
| Mean grader score G (15 tasks) | 0.866397 |
| Confirmed through the official entry (host) | 12 + 1 with a stub judge |
| Blocked before the grader by the missing judge key | 2 |
| Ever run inside the task verifier image (Docker, isolated VM) | 4 |
| Rubric tasks with a judge score | 0 of 14 |
| Rubric criteria weight covered by my reader | 1159 weight points over 323 criteria |

# Sources and supporting files

| | |
|---|---|
| **Dataset** | Physical Engineering's Last Exam, dev split, release 0.4.6 — 29 tasks, 33,416 files, 954,423,732 bytes. Local copy: /work/ple-dataset (README.md, release.json, task_cards.jsonl, tasks/). Access-gated; the repository asks that the data not be redistributed. |
| **Paper** | PLE: Physical Engineering's Last Exam, arXiv:2610.30537 (v2, 30 October 2026) — cited by the dataset README. |
| **Tooling** | Harbor task runner (github.com/laude-institute/harbor) and the PLE kit (github.com/google-research/ple, commit 8320f04) — the task folder format and the evaluation protocol. |
| **Working records** | /work/ple-solve/STATUS.md (chronological log), RESULTS_LEDGER.md (29-line ledger), NOTES_*.md (one per turn), ENV_523.md (host walls), census.json (grading types), report_data.json (the verified data layer of this report). |
| **Per-task results** | /work/ple-solve/<task>/results_523/RESULT.json — the final re-measurement of each machine-scored task, with sha256 before and after the run. Appendix A lists all fifteen. |
| **External normative sources used** | NFPA 70-2023 excerpts (Art. 336, 338.12(B)(2), 300.6(A), 110.26(E)), UFC 3-230-13, UFC 3-301-01, IEEE 1547.1, EDS-26, DAP-2 Appendix A, SRP-3/DI-01, ENG-PRC-014, TCS-02, RA-2025-07-01. Most are corpus documents; where a web copy was used it was registered as a source at the time and is named in the corresponding NOTES file. |
| **What is deliberately absent** | No credentials, tokens, keys or passwords appear in this report. The judge variables were never available and are referenced only by name. |

# Appendix A — measured score ledger

Every machine-scored task, with the file that sits on disk now. Sizes and sha256 were recomputed at report build time; G and R were re-read from each task's results_523/RESULT.json (or its paper_score.json) at the same moment. The full hash is given so a reader can verify a copy byte for byte.

| # | Task | File | Bytes | sha256 | G | R | Official | C |
|---|---|---|---|---|---|---|---|---|
| T-01 | cooling-water-flush-plan | `/work/cw/ws/output/submission.zip` | 10,349 | `ae3b5b76f6b3e500970a476de5557a2812a25e4b14738c52d7127a52d7f32076` | 0.923849 | 0.949233 | host test.sh | yes |
| T-02 | data-center-site-model | `/work/ple-solve/data-center-site-model/ws/submission/model.ifc` | 10,328 | `8b406beeecdaceee6664affbc116f9f5076d97bc7280e69353021728e0beb955` | 1.000000 | 1.000000 | host test.sh | — |
| T-03 | data-hall-device-takeoff | `/work/ple-solve/data-hall-device-takeoff/output/submission.zip` | 8,748 | `626f9303198adf4928a5421d4669f47049a1873b09beeb201648c8446e3b80ac` | 0.969898 | 0.969898 | host test.sh | — |
| T-04 | data-hall-mep-routing | `/work/ple-solve/data-hall-mep-routing/output/solution.py` | 33,315 | `1e1ab19a4b470608f5689961d8539d9b95145d1eaa96ba66ae3e805b30ba28cd` | 1.000000 | 1.000000 | host test.sh | — |
| T-05 | data-hall-mep-routing-offset | `/work/ple-solve/data-hall-mep-routing-offset/output/solution.py` | 37,507 | `1bdb60772d38119f422fb537352988abec5dfb0474e425cf652bf18a20464e2a` | 1.000000 | 1.000000 | host test.sh | — |
| T-06 | division-26-specifications | `/work/ple-solve/division-26-specifications/build/stage2/submission.zip` | 155,231 | `52e1b7f806ab3c528cf1ffe8595767a037e06e6308ecc95acaf349256813049c` | 1.000000 | 1.000000 | host test.sh | — |
| T-07 | frame-extension-method | `/work/ple-solve/frame-extension-method/out/pkg/submission.zip` | 14,375 | `9852b4598dc2fc5d869c5a96998b2aef656ac16446517bf27b088a7d8ad19209` | 0.758500 | 0.806800 | host test.sh | — |
| T-08 | heat-rejection-life-cycle-cost | `/work/ple-solve/heat-rejection-life-cycle-cost/out/submission.zip` | 100,582 | `2f5581ec1171c92d715b8e7eab9de09419bf29d72789a9bed913511d9630e361` | 1.000000 | 1.000000 | host test.sh | — |
| T-09 | mv-conveyance-study | `/work/ple-solve/mv-conveyance-study/build/submission.zip` | 64,509 | `1041555ac7a62b07c29de4d2d406387c99e489891607a63dc8bd0df51044f2f3` | 0.602449 | 0.701837 | host test.sh | — |
| T-10 | roof-deck-design | `/work/ple-solve/roof-deck-design/submission.zip` | 28,565 | `cda37f8626fa1478fa7e5811f216e6630d1199491b59009c407aad0b264f9a9d` | 0.839354 | 0.839354 | host test.sh | — |
| T-11 | seismic-diaphragm-shear | `/work/ple-solve/seismic-diaphragm-shear/submission.zip` | 38,498 | `b686556a2137f41be5d9739df9c1a1edd6286150ff8889d5ef36704793cff5f0` | 0.904833 | 0.904833 | host test.sh | yes |
| T-12 | wind-diaphragm-shear | `/work/ple-solve/wind-diaphragm-shear/out/submission.zip` | 54,244 | `34061c2f195f904cc562694c254e5f208dfb3f9af9e3c90f8f0babf0c1098566` | 0.762579 | 0.762579 | host test.sh | yes |
| T-13 | eor-review-corrections | `/work/ple-solve/eor-review-corrections/build/submission.zip` | 19,462 | `e616192c0212e0b8b6184e1bc4744bacf6bcba5bec95745d70ef1073a8578411` | 0.701612 | 0.879869 | host, stub judge | — |
| T-14 | foundation-strategy | `/work/ple-solve/foundation-strategy/out/submission.zip` | 33,276 | `6debcd3f2f5b2bd9348dccded6111637e804659f9fe4b3585e0b615c782d5aeb` | 0.847229 | 0.882547 | blocked by key | — |
| T-15 | lv-cable-sizing | `/work/lv-cable-sizing/build3/submission.zip` | 35,905 | `02e84d7896bd87d9c44f244caa3f7a6d3c7fbe53a4ef4d99663586f5da3ad13e` | 0.685658 | 0.892650 | blocked by key | yes |

C = ever run inside the task verifier image in Docker on the isolated VM. "blocked by key" means tests/test.sh exits before the grader because JUDGE_BASE_URL is unset; the grader part of those two tasks was measured directly (run_grade.py --no-judge + paper_score.py).

# Appendix B — rubric packages and their records

Fourteen documents, all hashed at build time. Criteria counts and weights are read from each task's tests/grader/criteria.json; the reader and breakage columns are the records written in the named NOTES file. No judge score exists for any row.

| # | Task | File | Bytes | sha256 | n | W | Reader | Breakages | Record |
|---|---|---|---|---|---|---|---|---|---|
| T-16 | backfeed-energization-reply | /work/ple-solve/backfeed-energization-reply/out/Halbray_Backfeed_Reply.docx | 43,451 | f5a90d94121dca7fe5f2fd435d3120d73396f5600f06e41d77f435758bb10f9a | 17 | 61 | 59/17 | 16/16 | NOTES_516.md |
| T-17 | emergency-spillway-check | /work/ple-solve/emergency-spillway-check/out/Memo_to_Callaway_Spillway_2026-10-31.docx | 46,094 | 4280fed48b650054a57c637bb657c315662e0bf0eff88861450674959946fb9b | 15 | 37 | 15/15 +5 | 20/20 | NOTES_510.md |
| T-18 | engineers-estimate-check | /work/ple-solve/engineers-estimate-check/out/Correspondence/Client/Memo_to_Callaway_2026-10-31.docx | 40,771 | fdf51ee0701297ff0ce1111b7f5328b4f30210a22a47f3bf9caa0e24423f81ab | 10 | 46 | 10/10 +4 | 12/12 | NOTES_509.md |
| T-19 | fill-compaction-acceptance | /work/ple-solve/fill-compaction-acceptance/output/Thelbridge_Materials_Acceptance_Fill_Compaction_2026-0708.docx | 42,525 | 5e6234c16d9b04ba8320f3f25faf190a9c5e6100ccd1484aa53053f3f6908bf7 | 28 | 108 | 28/28 +4 | 10/10 | NOTES_507.md |
| T-20 | fire-solve-convergence | /work/ple-solve/fire-solve-convergence/out/CFDME-2025-041_transient_solve_disposition_revA.docx | 50,471 | c1d6cdf28d5c274e29d3eaff551108bb692c61a2083b76a0d83ee61232aa65dd | 43 | 129 | 43/43 | 42/42 | NOTES_512.md |
| T-21 | fire-test-validation-memo | /work/ple-solve/fire-test-validation-memo/output/CFDME-2025-041_Validation_Memo_Section7.docx | 46,265 | 69daa3950ad8c9281fe7239bfe7d0de2b999450fc315874a2623bd06d46a71ec | 48 | 208 | 48/48 | 12/12 | NOTES_506.md |
| T-22 | footing-settlement-verification | /work/foot/out/Thelbridge_Verification_Memo_Item051_BlockC.docx | 17,638 | 54fd2aa41d8471f9b8832f75c4169b78f1ecc4a0c9c3fdff33123593fb2c9532 | 17 | 62 | 17/17 +5 | 20/20 | NOTES_511.md |
| T-23 | landscape-sheet-revision | /work/ple-solve/landscape-sheet-revision/output/DSR_Ph3_L4_Street_Tree_Memo_2026-10-31.docx | 41,169 | 1c7bed319668fa67eaa8ae8d4db0930754c44df959b34c5c28d2f7aba12b1148 | 18 | 77 | 18/18 | 11/12 (+1 equivalent) | NOTES_507.md |
| T-24 | les-mesh-resolution | /work/ple-solve/les-mesh-resolution/out/CFDME-2025-041_resolution_note_revA.docx | 43,314 | a0155983ffa83ae44ec18afc7dbdfbccf99d6facfe6c332e58257d9f338f0061 | 14 | 82 | 14/14 | 19/19 | NOTES_513.md |
| T-25 | permission-to-operate-memo | /work/ple-solve/permission-to-operate-memo/out/Corwyn_PTO_Memo.docx | 42,770 | 42b209e06c73411c7b70152f00931250a86a9a4c634b24b4c962c2202989329e | 13 | 44 | 11/13 | 16/16 | NOTES_515.md |
| T-26 | pre-application-capacity-response | /work/ple-solve/pre-application-capacity-response/out/ALN-108_PreApplication_Response.docx | 46,230 | ed8039a084c3e82672bb2ab04976ae3aba16d49408c058a9564c562d86d8cabb | 14 | 39 | 14/14 (39/39 W) | 12/12 | NOTES_517.md, NOTES_518.md |
| T-27 | shoring-design-verification | /work/ple-solve/shoring-design-verification/out/Thelbridge_Verification_Memo_Item048_BlockB.docx | 17,163 | a9c7569652780a51e50909b29bf08cddcdeb15ac0cc401d893bf48ab2ed9698d | 30 | 122 | 30/30 | 30/30 | NOTES_514.md |
| T-28 | solar-supplemental-review | /work/ssr/build/Bramwick_Commons_Screen_Memo.docx | 32,204 | 198adf5577db161dea2ea3ff93767c9bb887e5702471540d0fa8aa5b55feba77 | 22 | 77 | 22/22 | 21/21 | NOTES_519.md |
| T-29 | solar-witness-test-package | /work/wit/out/Municipal_Witness_Test_Package.docx | 45,225 | 7720499c855aca07a6475de615fbc27e6bf4a6aacfa44b6337c9a3783d060a19 | 34 | 67 | 30/30 +4/4 | 28/28 | NOTES_520.md |

n = number of criteria; W = sum of their numerical weights; Reader = criteria passed by my deterministic reader over the criteria it can express (see each task's section for what that means). Breakages were run through the official transform.py and the task's verify.py/grade.py with a stub judge.

# Appendix C — the host’s walls, measured

These are environment facts, not task facts. Each was measured, and each changed how a run had to be made.

| | |
|---|---|
| **/tmp and /root are mounted noexec** | test.sh’s Python shim cannot execute there; runs use TMPDIR=/work/tmp, and a uv-provided Python 3.11 was moved to /work/py311. |
| **The system Python lacks ezdxf and PyMuPDF** | The first official wind run scored 0.740356 instead of 0.762579 because two families failed; with the task’s requirements present the same test.sh gives 0.762579. |
| **data-center-site-model needs Python 3.11** | Its verifier image is python:3.11-slim and its wheels are cp311; a separate /work/venv311 was built from tests/grader_wheels. |
| **runuser lives only in /usr/sbin** | and /grader/logs must be writable by the grader user, otherwise test.sh exits with ERR_EXEC: PermissionError. |
| **No namespaces on the host** | unshare/clone of any namespace returns EPERM and CapEff lacks SYS_ADMIN/NET_ADMIN, so no container runtime can start here; Docker exists only on the isolated VM. |
| **The world image asks for 12,288 MB** | The isolated VM has 2 GB, so the benchmark’s world image cannot run there; the applications were assembled natively instead. |

# Appendix D — glossary

| | |
|---|---|
| **checks / rubric / checks-judge** | The three grading types. checks: deterministic grader only. rubric: an LLM judge scores weighted criteria. checks-judge: a grader plus a small number of judge families. |
| **p** | Fraction of constraint families that are both satisfied and registered (documented) in the package. |
| **h** | Fraction of hard families satisfied. In the paper rule a package with h < 1 scores zero objective. |
| **O and O′** | Objective ratio: the certified lower bound divided by the installed cost, then rescaled/calibrated by the task. O′ = 1 usually means “at or below the bound”, which is often unreachable by construction. |
| **Register** | A constraint register: one row per requirement, with the value and the document that evidences it. Graders score its precision and recall, and many hard families only count if registered. |
| **Rendering** | The form in which the judge reads a document: a PDF twin, a comments file, a style file, or a db_diff of the live applications. A rubric’s criteria name their renderings. |
| **db_diff** | A dump of the changes made in the live applications (work packages, comments, files). For three rubric tasks it is an input to the measurement: without it the whole run fails as RENDERING FAILED. |
| **Stub judge** | A mechanical server that answers the judge protocol with fixed replies. Used to prove wiring and weighting; never a measurement of quality. |
| **Mutation campaign** | Deliberate faults introduced one at a time into a package or a document; each is run through the real grader or reader. A fault the checks do not notice is either an equivalent change or a blind spot. |
| **Certified bound** | The lower bound the objective is measured against. In most tasks it is an LP or similar relaxation, not a buildable design, so a score of 1.0 can be impossible. |